Addendum for:
Skippers Dry Storage
1152 Perth Road
Troutman, NC 28166

Permit Number: 106916
Parcel Number: 4730-72-2809

Initial Dry Storage Building Expansion Plans: The following provisos shall be met in order to receive an Operation Permit by the Iredell County Health Department.

1. Facilities served include no changes in water use attributes (including no water use fixtures tied into the system to be provided in the dry stack buildings).

2. The system is designed for 200 new dry slips, 4 employees and 12 new wet slips with water reduction study for a total of 1500 gpd.

3. Water conserving fixtures are to be used in the two existing restrooms (toilets which use no more than 1.6 gallons per flush and automatically closing faucets which use no more that 1.0 gallons per minute).

4. Proposed marina pump out station is required to be constructed/installed prior to the new dry stack facilities becoming operational.

5. Septic Tank is to be modified to include at-grade or higher access manholes over each tank compartment, and the tank outlet modified to include an effluent filter (designed and installed per filter manufacturer's recommendation for this specific application).

6. The concrete slab over this (and the pump tank), as attached to plans received from B.K. Barringer, P.E. is NOT approved.

7. Pump Tank, including pump, discharge piping, disconnect, level control floats and float support/suspension, wiring and control panel are upgraded to be in accordance with current standards.

8. Relocated Supply Line shall be of ductile iron wherever it goes beneath existing or proposed areas subject to vehicular traffic unless the Supply Line is installed 36 inches deep or greater.

9. The applicant needs to meet setback requirements between system components and drainage features.