BLDR-2024-66897

ICHD - ENVIRONMENTAL HEALTH DIVISION

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625

PERMIT # OSWP-2025-71810

SEPTIC: IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4737-89-5725

APPLICANT / OWNER: AWT Inc. APPLICANT ADDRESS: 501 N Salem Street, Suite 203 Apex, NC 27502

SITE ADDRESS: 113 HOMEWOOD LN, STATESVILLE, NC 28625 PHONE: (704) 268-9160 ALT. PHONE:

SITE DIRECTIONS: S Chipley Ford to Bluegill to Homewood Lane SAP CONTROLLED: YES ☐ NO ☑

SUBDIVISION: Poplar Ridge SECTION: LOT #: 55 LOT AREA: 1.518 DESIGN FLOW: 480 L.T.A.R.: 0.3

Septic Tank: 1000 (gal)	STB: 760	Date: –	☒ New System ☐ Repair ☐ Expansion	System Type: II	☐ Residence	No. Bedrooms: 4	Water Supply: Municipal Water
Pump Tank: (gal)	PT:	Date:	System Description: Type IIb, gravity distribution to 25% reduction drain field product.		☐ Business	No. Persons: 8	
Pump Make:	Model:	Serial #:	Repair System Description: Type IIb, pump to 25% reduction drain field product.		☐ Other	No. Employees:	
# Nitrification Fields: 1	# Lines: 3	Linear Ft.: 402	Maintenance Agreement Required: ☐ YES ☑ NO		☑ Slab	☐ Crawl Space	
Trench Width: 36	Trench Bottom Depth (Low side): 31		Gravel Depth:	☑ GRAVITY ☐ PRESSURE	☐ Basement w/ Plumbing	☐ Basement w/o Plumbing	

Comments / Conditions:

INITIAL SITE SKETCH

See attached.

AS BUILT SKETCH

3/4/2025 - Inspection performed by Matthew Wilkinson

REHS 3061 : inspected tank - lines - proper fall achieved. - ST 7ft from Home

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT with plat valid without expiration. ☑ IMPROVEMENT PERMIT with site plan valid for 60 mos. ☑ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.

Owner / Applicant Signature: ☒ Date:

IMPROVEMENT PERMIT by: Benjamin A Bell Date: 3/20/2025

AUTHORIZATION TO CONSTRUCT by: Benjamin A Bell Date: 3/20/2025

Installed By: Rowan Septic

OPERATION PERMIT by: Benjamin A Bell Date: 3/20/2025

Existing System Inspected By: Date:

IREDELL COUNTY HEALTH DEPARTMENT
BRADY FREEMAN REHS MS
HEALTH DIRECTOR

Public Health
Prevent. Promote. Protect.
Iredell County Health Department

Notice of Intent to SUSPEND/REVOKE Improvement Permit/Construction Authorization
3/20/2025

Owner: AWT Inc
Address: 501 N salem St Suite 203 Apex NC 27502

Subject: Notice of Intent to Revoke/Suspend :113 Homewood Ln Statesville NC 28625

Dear AWT Inc:
(Owner's Name)

The Iredell County Health Department (ICHD) inspected the site for the on-site wastewater system located 113 Homewood Lane Statesville NC for compliance with the Laws (Article 11 of Chapter 130A of the North Carolina General Statutes), Rules (15A NCAC 18A .1900 et seq.), and Improvement Permit/Construction Authorization III determined the following violations:

Violation	Law or Rule Citation
Change in design; originally design for pump- gravity system installed	

This is to notify you that based on these violations, the Department intends to suspend/revoke (specify) your Improvement Permit/Construction Authorization (specify) 30 days from the date of this notice.

If the ICHD determines that all of the violations have been corrected before thirty (30) days expire, the suspension/revocation (specify) will not go into effect. *[Insert for suspension]* If the permit is suspended, the health department must determine that the violations have been corrected before the suspension will be lifted. *[Insert for revocation]* If the permit is revoked, you must apply for a new Improvement Permit/Construction Authorization and meet the requirements of the current laws and rules necessary to obtain a new IP/CA.

You have a right to an informal review of this decision. You may request an informal review by the environmental health supervisor at the local health department. You may also request an informal review by the NC Department of Health and Human Services Regional Soil Scientist. A request for informal review must be made in writing to the local health department.

You also have a right to a formal appeal of this decision. To pursue a formal appeal, you must file a petition for a contested case hearing with the Office of Administrative Hearings, 6714 Mail Service Center, Raleigh, NC 27699-6714. You may write the Office of Administrative Hearings, call the office at (919) 431-3000 or get a copy of the petition form from the OAH web site at http://www.ncoah.com/forms.html. The petition for a contested case hearing must be filed in accordance with the provision of North Carolina General Statutes 130A-24 and 150B-23 and all other applicable provisions of Chapter 150B. North Carolina General Statute 130A-335 (g) provides that your hearing would be held in the county where your property is located.

If you wish to pursue a formal appeal, you must file the petition form with the Office of Administrative Hearings **WITHIN 30 DAYS OF THE DATE OF THIS LETTER.** The date of this letter is 3/20/2025 Meeting the 30 day deadline is critical to your formal appeal.

If you file a petition for a contested case hearing with the Office of Administrative Hearings, you are required by law (NC General Statute 150B-23) to serve a copy of your petition on the Office of General Counsel, NC Department of Health and Human Services, 2001 Mail Service Center, Raleigh, NC 27699-2001.

Do not serve the petition on your local health department. Sending a copy of your petition to the local health department will not satisfy the legal requirement in NC General Statute 150B-23 that you send a copy to the Office of General Counsel, 2001 Mail Service Center, NC Department of Health and Human Services.

You may contact our office at 704-878-5305 x3456 or by fax at 704-871-3483.

Sincerely,

Benjamin A Botkins
Signature of DHHS Authorized Agent

Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

LETTER TO REVOKE AOWE PERMIT
113 Homewood Lane, Statesville, NC. 28625

PREPARED FOR: Iredell County

PREPARED BY: Jeff Vaughan, Senior Agronomist & Soil Scientist

DATE: March 12, 2025

To whom it may concern,

This letter is to facilitate the revocation of the existing AOWE septic permit on file for the home located at 113 Homewood Lane, Statesville, NC, PIN# 4737895725. AWT hereby officially revokes the existing septic permit in order to re-submit an amended version of the AOWE package for permitting.

Sincerely,

Jeff Vaughan, AOWE

Docusign Envelope ID: E620C034-F09E-488C-8BDD-77295A41D19A

OSWP 2025-7180

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK BENTON • Chief Deputy Secretary for Health
SUSAN KANSAGRA • Assistant Secretary for Public Health
Division of Public Health

Application for Services

This application, in conjunction with the common form established in G.S. 130A-335(a3) and (a5), is optional for local health departments to be used for applications submitted in accordance with G.S. 130A-335(a2), (a3), and (a5).
[hereinafter, G.S. 130A-335(a3) and (a5) permits referred to as (a2) Improvement Permit and (a2) Construction Authorization]

Applying for:
☑ (a2) Improvement Permit ☑ (a2) Construction Authorization ☐ (a2) Repair/Construction Authorization

If applying for a Construction Authorization, please indicate desired system type(s):
☐ Accepted ☐ Conventional ☐ Innovative ☑ Other Type IIb, 25% reduction drain field product. ☐ Any

☑ New Construction ☐ Expansion ☐ System Relocation ☐ Change of Use ☐ Repair
☑ 5-Year Expiration Requested (site plan provided) ☐ Non-Expiring Permit Requested (plat provided, defined in G.S.130A-334(7a)
Requesting DHHS review? (systems >3000 GPD or IPWW) ☐ Yes ☑ No

Applicant: Trevor Hackney
Mailing Address: 501 N. Salem Street
City: Apex
State: NC Zip: 27502
Phone #: (704)268-9160
Email: thackney@agriwaste.com

Owner: RoCo Builders LLC
Mailing Address: 355 Country Ridge Rd
City: Rockwell
State: NC Zip: 28138
Phone #: 704-408-2301
Email: enewtonsc4@gmail.com

If the answer to any of the following questions is "yes", applicant must attach supporting documentation.

☐ Yes	☒ No	Does the site contain any jurisdictional wetlands?
☐ Yes	☒ No	Is any wastewater going to be generated on the site other than domestic sewage?
☐ Yes	☒ No	Is the site subject to approval by any other public agency?
☐ Yes	☒ No	Are there any easements or right of ways on this property?

I understand that the documentation and fees, as required in G.S. 130A-335(a2), (a3), (a5), and (a6), attached to this application are to be used to issue an Improvement Permit and/or Construction Authorization pursuant to G.S. 130A-335(a2),(a3), and (a5). I understand that authorized county and state officials are granted right of entry to the property indicated on this application to conduct necessary inspections to determine compliance with applicable laws and rules. ***I understand that if the information in the application for an Improvements Permit and/or Construction Authorization is falsified, changed, or the site is altered, then the Improvement Permit and Construction Authorization shall become invalid.***

Applicant Signature: Trevor Hackney Date: 11/14/2024

Owner's Signature: DocuSigned by: Evan Newton 2E6776D37BF8451... Date: 11/22/2024

Permit/File #: OSWP-2025 71810

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES

ROY COOPER • Governor
KODY H. KINSLEY • Secretary
MARK BENTON • Chief Deputy Secretary for Health
SUSAN KANSAGRA • Assistant Secretary for Public Health
Division of Public Health

Submittal Includes: ■ (a2) Improvement Permit ■ (a2) Construction Authorization ☐ Fee $_____

IMPROVEMENT PERMIT FOR G.S. 130A-335(a2)

County: Iredell
PIN/Lot Identifier: 4737895725
Issued To: RoCo Builders LLC
Property Location: 113 Homewood Lane, Statesville, NC.28625
Subdivision (if applicable) Poplar Ridge Lot #: 55 Block: N/A Section: N/A
LSS Report Provided: Yes ■ No ☐
If yes, name and license number of LSS: Jeff Vaughan, 1227

New ■ Expansion ☐ System Relocation ☐ Change of Use ☐
Facility Type: Single Family Residence
Number of bedrooms: 4 Number of Occupants: 8 Other: _____
Design Wastewater Strength: ■ Domestic ☐ High Strength ☐ Industrial Process Wastewater
Proposed Design Daily Flow: 480 GPD Proposed LTAR (Initial): 0.3 Proposed LTAR (Repair): 0.3
Proposed Wastewater System Type*: Type IIb, gravity to 25% reduction drain field product. (Initial) Pump Required: ☐ Yes ■ No ☐ May be required
Proposed Wastewater System Type*: Type IIIb, pump to 25% reduction drain field product. (Repair) Pump Required: ■ Yes ☐ No ☐ May be required
**Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*
Effluent Standard: ■ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCW
Saprolite System (Initial): ☐ Yes ■ No Saprolite System (Repair): ☐ Yes ■ No
Fill System (Initial): ☐ Yes ■ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)
Fill System (Repair): ☐ Yes ■ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)
Usable Depth to LC (Initial)[x]: 43" Usable Depth to LC (Repair)[x]: 43" ***[x] Limiting Condition***
Max. Trench Depth (Initial)[‡]: 31" Max. Trench Depth (Repair)[‡]: 31" ***[‡] Measured on the downhill side of the trench***
Artificial Drainage Required: ☐ Yes ■ No If yes, please specify details: _____
Type of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ■ Municipal Supply ☐ Spring ☐ Other: _____
Drainfield location meets requirements of Rule .0508: Yes ■ No ☐ Drainfield location meets requirements of Rule .0601: Yes ■ No ☐
Permit valid for: ■ Five years [site plan submitted pursuant to GS 130A-334(13a)] ☐ No expiration [plat submitted pursuant to GS 130A-334(7a)]

Permit conditions:

Licensed Soil Scientist Print Name: Jeff Vaughan
Licensed Soil Scientist Signature: _____ Date: 03/12/2025

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

See attached site sketch

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES
Division of Public Health

Permit/File #: OSWP-2025 71810

This Section for Local Health Department Use Only

Initial submittal received: 3/17/2025 (Date) by BB. (Initials)

G.S. 130A-335(a3) states the following:

When an applicant for an Improvement Permit submits to a local health department an Improvement Permit application, the permit fee charged by the local health department, the common form developed by the Department, and a soil evaluation pursuant to subsection (a2) of this section, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Improvement Permit includes all of the required components. If the local health department determines that the Improvement Permit is incomplete, the local health department shall notify the applicant of the components needed to complete the Improvement Permit. The applicant may submit additional information to the local health department to cure the deficiencies in the Improvement Permit. The local health department shall make a final determination as to whether the Improvement Permit is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The Department shall develop a common form for use as the Improvement Permit.

The review for completeness of this Improvement Permit was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

_____

_____

Copies of this were sent to the LSS and the Applicant on _____ (Date)

State Authorized Agent: _____ Date: _____

☑ Complete

State Authorized Agent: Benjamin A Bolton Date: 3/20/2025

This Improvement Permit is issued pursuant to G.S. 130A-335 (a2) and (a3) using the signed and sealed LSS/LG evaluation(s) attached here. The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. *This permit is subject to revocation if the site plan, plat, or the intended use changes.* The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to evaluations, submittals, or actions from a licensed soil scientist or licensed geologist pursuant to GS 130A-335(a2).

Improvement Permit Expiration Date: 3/20/2030

See attached site sketch

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES
Division of Public Health

Permit/File #: OSWP-2025 71810

CONSTRUCTION AUTHORIZATION FOR G.S. 130A-335(a2)

County: Iredell **Pre-Construction Conference Required:** Yes ☒ No ☐

PIN/Lot Identifier: 4737895725

Issued To: RoCo Builders LLC

Property Location: 113 Homewood Lane, Statesville, NC.28625

AOWE/PE Plans/Evaluations Provided: Yes ☒ No ☐ If yes, name and license number of AOWE/PE: Jeff Vaughan, 10003E

Facility Type: Single Family Residence

Number of bedrooms: 4 Number of Occupants: 8 Other: _____

☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No

Crawl Space? ☐ Yes ☒ No Slab Foundation? ☒ Yes ☐ No

Type of Wastewater System* Type IIb, gravity to 25% reduction drain field product. (Initial) Type IIIb, pump to 25% reduction drain field product. (Repair)

**Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*

Design Daily Flow: 480 GPD Wastewater Strength: ☒ Domestic ☐ High Strength ☐ Industrial Process WW

Session Law 2014-120 Section 53, Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies? ☐ Yes ☒ No
(if yes, please provide engineering documentation)

Effluent Standard: ☒ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCW

Type of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ☒ Municipal Supply ☐ Spring ☐ Other: _____

Installation Requirements/Conditions

Septic Tank Size: 1,000 gallons Total Trench/Bed Length: 402 feet Trench/Bed Spacing: 9 feet on center

Trench/Bed Width: 36 inches LTAR: 0.3 gpd/ft² Usable Depth to LC (Initial)[x]: 43" [x] ***Limiting condition***

Soil Cover: - inches Slope Corrected Maximum Trench/Bed Depth[‡]: 31" inches [‡] ***Measured on the downhill side of the trench***

Pump Tank Size (if applicable): - gallons Requires more than 1 pump? ☐ Yes ☒ No

Pump Requirements: - ft. TDH vs. - GPM Grease Trap Size (if applicable): - gallons

Distribution Method: ☐ Serial ☒ D-Box or Parallel ☐ Pressure Manifold(s) ☐ LPP ☐ Other: _____

Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details: _____

Legal Agreements *(If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)*

Multi-party Agreement Required [.0204(g)]: ☐ Yes ☒ No Declaration of Restrictive Covenants: ☐ Yes ☒ No

Easement, Right-of-Way, or Encroachment Agreement Required [.0301(b)]: ☐ Yes ☒ No

Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements: _____

Permit conditions:

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. *This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes.* The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

AOWE/PE Print Name: Jeff Vaughan

AOWE/PE Signature: _____ Date: 03/12/2025

This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).

See attached site sketch

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES
Division of Public Health

Permit/File #: OSWP-2025 11410

This Section for Local Health Department Use Only

Initial submittal received: 3/17/2025 (Date) by BB (Initials)

G.S. 130A-335(a5) states the following:

When an applicant for a Construction Authorization, or an Improvement Permit and Construction Authorization together, submits a Construction Authorization, or an Improvement Permit and Construction Authorization application together, the permit fee charged by the local health department, the common form developed by the Department, and any necessary signed and sealed plans or evaluations conducted by a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Construction Authorization or Improvement Permit and Construction Authorization includes all of the required components. If the local health department determines that the Construction Authorization or Improvement Permit and Construction Authorization is incomplete, the local health department shall notify the applicant of the components needed to complete the Construction Authorization or Improvement Permit and Construction Authorization. The applicant may submit additional information to the local health department to cure the deficiencies in the Construction Authorization or Improvement Permit and Construction Authorization. The local health department shall make a final determination as to whether the Construction Authorization or Improvement Permit and Construction Authorization is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The applicant may apply for the building permit for the project upon the decision of completeness of the Construction Authorization or Improvement Permit and Construction Authorization by the local health department or if the local health department fails to act within five business days. The Authorized On-Site Wastewater Evaluator or licensed engineer submitting the evaluation pursuant to this subsection may request that the local health department revoke or suspend the Construction Authorization or Improvement Permit and Construction Authorization for cause. Upon written request of the Authorized On-Site Wastewater Evaluator or licensed engineer, the local health department shall suspend or revoke the Construction Authorization or Improvement Permit and Construction Authorization pursuant to G.S. 130A-23. The Department shall develop a common form for use as the Construction Authorization.

The review for completeness of this Construction Authorization was conducted in accordance with G.S. 130A-335(a5). This Construction Authorization is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing: _____

_____

Copies of this were sent to the AOWE/PE and the Applicant on _____ (Date)

State Authorized Agent: _____ Date: _____

☒ Complete

State Authorized Agent: Bijan H Bobb Date of Issuance: 3/20/2025

This Construction Authorization is issued pursuant to G.S. 130A-335(a2) and (a5) using the signed and sealed plans or evaluations attached here. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to plans, evaluations, preconstruction conference findings, submittals, or actions from a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator in GS 130A-335(a2), (a5), and (a7). The Department, the Department's authorized agents, and the local health departments shall be responsible and bear liability for their actions and evaluations and other obligations under State law or rule, including the issuance of the operations permit pursuant to GS 130A-337.

Construction Authorization Expiration Date: 3/20/2030

See attached site sketch

AGRITEC-01 CGARKALNS

CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 1/12/2024

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Hartsfield & Nash Agency, Inc. 10405 Ligon Mill Rd., Ste H Wake Forest, NC 27587	CONTACT NAME: Connie Garkalns PHONE (A/C, No, Ext): (919) 556-3698 FAX (A/C, No): (919) 556-8758 E-MAIL ADDRESS: Connie@hartsfield-nash.com
INSURED Agri-Waste Technology Inc 501 N. Salem St Ste 203 Apex, NC 27502	INSURER(S) AFFORDING COVERAGE — NAIC # INSURER A : Selective Insurance Company of the Southeast — 39926 INSURER B : ACCIDENT FUND INSURANCE COMPANY OF AMERICA — 10166 INSURER C : Evanston Insurance Company — 35378 INSURER D : INSURER E : INSURER F :

COVERAGES **CERTIFICATE NUMBER:** **REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS	
A	X COMMERCIAL GENERAL LIABILITY CLAIMS-MADE X OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: POLICY X PRO-JECT LOC OTHER:			S 2253659	1/18/2024	1/18/2025	EACH OCCURRENCE DAMAGE TO RENTED PREMISES (Ea occurrence) MED EXP (Any one person) PERSONAL & ADV INJURY GENERAL AGGREGATE PRODUCTS - COMP/OP AGG	$ 2,000,000 $ 300,000 $ 10,000 $ 2,000,000 $ 4,000,000 $ 4,000,000
A	AUTOMOBILE LIABILITY X ANY AUTO OWNED AUTOS ONLY SCHEDULED AUTOS HIRED AUTOS ONLY NON-OWNED AUTOS ONLY			S 2253659	1/18/2024	1/18/2025	COMBINED SINGLE LIMIT (Ea accident) BODILY INJURY (Per person) BODILY INJURY (Per accident) PROPERTY DAMAGE (Per accident)	$ 1,000,000 $ $ $
A	UMBRELLA LIAB X OCCUR EXCESS LIAB CLAIMS-MADE DED RETENTION $			S 2253659	1/18/2024	1/18/2025	EACH OCCURRENCE AGGREGATE	$ 2,000,000 $ 2,000,000
B	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) Y/N: N If yes, describe under DESCRIPTION OF OPERATIONS below	N / A		100003072	1/18/2024	1/18/2025	X PER STATUTE OTH-ER E.L. EACH ACCIDENT E.L. DISEASE - EA EMPLOYEE E.L. DISEASE - POLICY LIMIT	$ 1,000,000 $ 1,000,000 $ 1,000,000
C	Prof & Pollution			MKLV3ENV104078	8/22/2023	8/22/2024	Each Claim	5,000,000
A	Leased / Rented			S 2253659	1/18/2024	1/18/2025	Equipment	25,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

CERTIFICATE HOLDER

***This is ONLY For Informational Purposes
Contact Agency for Specific Holder info to be added
****

CANCELLATION

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

Connie Garkalns

© 1988-2015 ACORD CORPORATION. All rights reserved.
The ACORD name and logo are registered marks of ACORD

Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

Soil Suitability for Domestic Sewage Treatment and Disposal Systems
113 Homewood Lane, Statesville, NC. 28625
(Iredell County PIN: 4737895725)

PREPARED FOR: RoCo Builders LLC – Client

PREPARED BY: Jeff Vaughan, Senior Agronomist & Soil Scientist
Trevor Hackney, Environmental Scientist

DATE: March 12, 2025

Soil suitability for domestic sewage treatment and disposal systems was evaluated on October 30, 2024, for the property located at 113 Homewood Lane, Statesville, NC. Trevor Hackney and Nathan Estevez of Agri-Waste Technology, Inc. (AWT) conducted the soil evaluation. This evaluation was done to facilitate permitting for a septic system. This report and attached documents were prepared to meet the requirements for G.S. 130A-335(a2).

A drawing of the site plan, septic layout, and boring locations is included in Attachment 1. Profile descriptions for each boring are included in Attachment 2. Additional documentation about the property is included in Attachment 3.

The total property area is approximately 1.5 acres and is entirely wooded. The home is proposed towards the front of the property and the septic system is proposed behind the home. The home will be served by public water. The proposed primary septic system is a type IIb septic system, gravity distribution utilizing a 25% reduction drain-field product. The repair system will be a type IIIb septic system, pump to 25% reduction drain field product.

Soil Suitability for Domestic Sewage Treatment and Disposal Systems
The drawing in Attachment 1 details the property boundaries, soil boring locations, and layout of drain field trenches (Completed by AWT). Soil borings were examined to determine soil suitability for on-site sewage disposal systems in accordance with 15A NCAC 18E Rules for Wastewater Treatment and Disposal Systems. These borings were advanced with a hand auger.

A septic layout was performed to demonstrate available space (.0508). The layout in Attachment 1 indicates there is available space for a four-bedroom primary and repair system utilizing a 25% reduction drain-field product for the primary and repair septic system.

The proposed LTAR (Long Term Acceptance Rate) by AWT is 0.3 GPD/ft^2. The soils on this property are group IV soils within the distribution and treatment zone as used to define the LTAR. With an LTAR of 0.3 GPD/ft^2, 800 linear feet of trench are necessary to support a four-bedroom home initial and repair systems. The attached drawing proves that 402 linear feet of trench can be installed for the primary septic system. The attached drawing proves that 400 linear feet of trench can be installed for the repair septic system. Since usable slope corrected soil depths meet or exceed 43", the maximum low side trench bottom should not exceed 31". AWT is recommending the use of a 25% reduction drain field product.

Any disturbances or grading done in the usable area or within the proposed setbacks will change the potential of using the area designated for a drain field.

We appreciate the opportunity to assist you in this matter. Please contact us with any questions, concerns, or comments.

Sincerely,

Jeff Vaughan, LSS/AOWE



Attachment 1: Drawings & Calculations


ROCO BUILDERS - HOMEWOOD LN

Project Location
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-408-2301
enewtonsc4@gmail.com

Project Consultant
Jeff Vaughan, L.S.S
(919) 367-6313
Agri-Waste Technology, Inc.
501 N. Salem Street, Suite 203
Apex, NC 27502
(919) 859-0669
(919) 233-1970 Fax

System Overview
Single Family Residence
4 Bedroom, 480 gpd
Chambers Dispersal Primary
Chambers Dispersal Repair
Distribution Box Distribution Primary
Pressure Manifold Distribution Repair



VICINITY MAP

Sheet Index

Sheet 1	Cover Sheet
Sheet 2	Property Layout
Sheet 3	Component Layout
Sheet 4	Primary Drainfield
Sheet 5	Repair Drainfield
Sheet 6	Detail Sheet 1
Sheet 7	Detail Sheet 2
Sheet 8	Excavation Safety

AWT
Engineers and Soil Scientists
Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-408-2301
enewtonsc4@gmail.com


FOR REVIEW ONLY

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
COVER SHEET

Drawn By:	Drawn On:
D. Harkins	10.31.2024
Revised By:	Revised On:
—	—
Released By:	Released On:
—	—

Drawing Number:
WW-1



NOTE
ELEVATION CONTOURS ARE FROM GIS DATA AND MAY NOT ACCURATELY REFLECT THE ACTUAL GROUND SURFACE OR RECENT GRADING OPERATIONS.
PARCEL BOUNDARY VIA PIEDMONT DESIGN ASSOCIATES, P.A.
GRAVITY DISTRIBUTION TO PRIMARY DRAINFIELD MAY BE POSSIBLE IF FINAL GRADE ALLOWS

1 WW-2 N.T.S. PROPERTY LAYOUT
SOURCE: AWT, Inc.

AWT
Engineers and Soil Scientists
Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-408-2301
enewtonsc4@gmail.com

For Review Only


REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
Property Layout

DRAWN BY:	CREATED ON:
D. Harkins	10.31.2024
REVISED BY:	REVISED ON:
—	—
RELEASED BY:	RELEASED ON:
—	—

DRAWING NUMBER
WW-2

NOTE:
GRAVITY DISTRIBUTION MAY BE POSSIBLE IF FINAL GRADE ALLOWS
CONTRACTOR TO ADJUST TANK PLACEMENTS AS NECESSARY TO MAINTAIN:
1. 15' DOWNSLOPE, 10' SIDESLOPE, AND 10' UPSLOPE SETBACK FROM FOUNDATION DRAIN
2. MIN. 12" COVER OVER SEPTIC TANK (NOT TO EXCEED 36")
3. MIN. 18" COVER OVER PIPES
4. MIN. 2% GRADE ON GRAVITY PIPE FROM HOUSE TO SEPTIC TANK



LEGEND

CO	Cleanout
CP	Control Panel
EF	Effluent Filter
FSL	Field Supply Line, 2" Sch40 PVC
PT	Pump Tank, 1250 gal
SB	Splice Box
ST	Septic Tank, 1000 gal
SW	Sewer, 4" Sch40 PVC

WW-3 N.T.S. COMPONENT LAYOUT
SOURCE: AWT, INC.

AWT
Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-406-2301
enewtonsc4@gmail.com

For Review Only

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
Component Layout

DRAWN BY:	CREATED ON:
D. Harkins	10.31.2024
REVISED BY:	REVISED ON:
—	—
RELEASED BY:	RELEASED ON:
—	—

DRAWING NUMBER
WW-3

General Drainfield Notes:

1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

NOTE:
Gravity distribution to distribution box may be possible if final grade allows.

Line	Use	Color	Elevation	Length	Primary	Repair
1	Layout Line	White		105		98.0
2	Layout Line	Purple		126		98.0
3	Layout Line	Blue		166		102.0
4	Layout Line	White		62		
5	Layout Line	Purple		253		102.0
6	Layout Line	Blue		205	134.0	
7	Layout Line	Purple		156	134.0	
8	Layout Line	White		200	134.0	
9	Layout Line	Purple		74		
10	Layout Line	Blue		52		
11	Layout Line	White		29		
			Total	1428	402	400



1 WW-4 Primary Drainfield

SOURCE: Agri-Waste Technology, Inc.

AWT
Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.559.9669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-408-2301
enewtonsc4@gmail.com

For Review Only

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
Primary Drainfield

DRAWN BY:	CREATED ON:
D. Harkins	10.31.2024
REVISED BY:	REVISED ON:
—	—
RELEASED BY:	RELEASED ON:
—	—

DRAWING NUMBER
WW-4

General Drainfield Notes:

1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

DRAINFIELD INFO. - **Repair**

Proposed Type of System/Distribution: ***Pump to Pressure Manifold using Chambers***

Line No.	Flag Color	Line Length (ft.)		Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
1	White	98	1/2in SCH 80	5.48	0.056	0.408
2	Purple	98	1/2in SCH 80	5.48	0.056	0.408
3	Blue	102	1/2in SCH 80	5.48	0.054	0.392
5	Purple	102	1/2in SCH 80	5.48	0.054	0.392
	Total	**400**	**Total**	**21.92**	**Avg.**	**0.40**



1 WW-5 Repair Drainfield

SOURCE: Agri-Waste Technology, Inc.

AWT Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-406-2301
enewtonsc4@gmail.com


For Review Only

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
Repair Drainfield

DRAWN BY: D. Harkins	CREATED ON: 10.31.2024
REVISED BY: —	REVISED ON: —
RELEASED BY: —	RELEASED ON: —

DRAWING NUMBER
WW-5




SHOAF PRECAST SEPTIC INC.	**MODEL: TS 1000 STB NON TRAFFIC 1000 Gallon Septic Tank**
4130 WEST US HWY 64	
LEXINGTON, NC 27295	
PHONE (336) 787-5826	
FAX (336) 787-2826	
WWW.SHOAFPRECAST.COM	
SHOAF-1,000 SEPTIC TANK	
STB-347 NON TRAFFIC	
LIQUID CAPACITY-1,000 GALLONS/AIRSPACE-10"	
TANK HEIGHT-67.5"	
BOTTOM OF TANK TO CENTER OF INLET-59"	
BOTTOM OF TANK TO CENTER OF OUTLET-57"	
LENGTH TO WIDTH RATIO-2 TO 1	
SIZE OF INLET & OUTLET-4" PIPE	
TYPE OF INLET & OUTLET-PGLYLOCK OR EQUAL (MEETS ASTM C-923)	
CONCRETE PSI-4000; TANK WEIGHT- 10,500 LBS.	
REINFORCEMENT PER STATE CODE	

SCALE - N.T.S.

1 WW-6 N.T.S. SEPTIC TANK (OR EQUIVALENT 1,000-GAL TANK)


SOURCE: Shoaf Precast Septic Inc.



NOTES:
1. Mound backfill above the Natural Ground Surface to allow for settlement.
2. Perforated corrugated plastic pipe shall meet requirements of ASTM D 2729.
3. Pipe shall be level, 0.00% slope.
4. End cap shall be provided at end of all corrugated plastic lines.
5. Trench bottom shall be level.

2 WW-6 N.T.S. CHAMBERS - TRENCH CROSS-SECTION (TYPICAL)


INFILTRATOR Water Technologies, LLC



Install Safety Net in Each Access Riser that does not contain an Inner Lid

RISER INSTALLATION INSTRUCTIONS:

1. Prep Adapter Channel & Riser
   - 1.1. Roughen the bonding surfaces of the adapter and riser with sandpaper.
   - 1.2. Use a clean cloth and acetone or alcohol to clean the bonding surfaces of the adapter and riser. The bonding surfaces must be clean and dry for a good fit and watertight joint. Let the acetone or alcohol dry completely.
2. Apply Adhesive
   - 2.1. Apply a bead of methacrylate adhesive to the outside of the adapter. One 7-oz packet of MA320 adhesive is typical for one 24" riser.
3. Install Riser
   - 3.1. If the riser has penetrations, align the riser correctly.
   - 3.2. Firmly press the riser onto the adapter until the bottom of the riser is resting on the concrete (cast-in-adapters) or the adapter flange (bolted-down adapters). Twist the riser back and forth slightly to fully seat it on to create a good bond.
   - 3.3. Apply a bead of methacrylate adhesive to the inside of the access riser-adapter joint.
   - 3.4. Use a tongue depressor, putty knife, or clean cloth to make a continuous fillet on the inside of the access riser-adapter joint.
   - 3.5. Apply hydraulic cement to bond outer riser seat and top of tank.
4. Ensure safety net and inner lid are in place and secured.



NOTE: Install 4 Ring Clamps if 8" (or larger) Filter is Used

FOR RISER WALL PENETRATIONS	
Grommet Size, Inches (Nominal IPS Pipe Size)	Hole Saw Size, Inches
1/2	1
3/4	1 1/4
1	1 9/16
1 1/4	1 3/4
1 1/2	2 1/8
2	2 3/4
3	3 7/8
4	5

3 WW-6 N.T.S. RISER SAFETY NETS

SOURCE: SIM-TECH, Inc.

NOTES

1. INSTALLATION TO FOLLOW ALL NC DHHS AND Iredell COUNTY APPLICABLE RULES AND REGULATIONS.
2. Iredell COUNTY TO PERFORM CONSTRUCTION INSPECTIONS AND FINAL SYSTEM CERTIFICATION.
3. SEPTIC TANK TO HAVE APPROVED EFFLUENT FILTER.
4. CONTRACTOR TO ABIDE BY ALL SAFETY REGULATIONS DURING SYSTEM INSTALLATION.
5. CONTRACTOR SHALL BACKFILL AROUND ALL ACCESS AREAS SUCH THAT STORM WATER IS SHED AWAY FROM POTENTIAL ENTRY POINTS.
6. INVERT ELEVATIONS OF ALL COMPONENTS TO BE VERIFIED IN FIELD BY CONTRACTOR TO INSURE PROPER OPERATION.
7. ALL SYSTEM PIPING TO BE SCH40 PVC (EXCEPT WHERE NOTED).
8. ALL GRAVITY ELBOWS TO BE LONG RADIUS OR LONG SWEEPING TYPE ELBOWS.
9. ACTUAL INSTALLATION AND PLACEMENT OF TREATMENT SYSTEM TO BE OVERSEEN BY CONTRACTOR.
10. TANKS TO BE SET ON 6" MINIMUM GRAVEL BASE. USE #5 OR #57 STONE FOR BASE.
11. CONTRACTOR TO SEED AND/OR MULCH DISTURBED AREAS TO COINCIDE WITH EXISTING LANDSCAPE. AREA SHALL NOT BE LEFT WITH UNCOVERED SOIL.
12. ALL RISERS TO HAVE CAST-IN-PLACE TANK ADAPTERS AND BE SINGLE-PIECE RISER. RISERS TO EXTEND 6" ABOVE SOIL SURFACE AND BE DESIGNED TO PREVENT SURFACE WATER INFLOW.
13. BACKFILL AROUND TANK(S) SHALL BE GRAVEL OR TANK HOLE SHALL BE OVER-EXCAVATED A MINIMUM OF 2' IN ALL DIRECTIONS TO ALLOW FOR MECHANICAL TAMPING OF BACKFILL.
14. ALL PENETRATIONS TO BE SEALED.
15. SPIGOT TO BE LOCATED ON OUTSIDE OF BUILDING WITHIN 50' OF TANKS.
16. CONTRACTOR TO ADJUST TANK PLACEMENT TO MEET SITE CONSTRAINTS.

AWT
Engineers and Soil Scientists
Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-408-2301
enewtonsc4@gmail.com

FOR REVIEW ONLY

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE
DETAIL SHEET 1

DRAWN BY: D. Harkins	CREATED ON: 10.31.2024
REVISED BY: —	REVISED ON: —
RELEASED BY: —	RELEASED ON: —

DRAWING NUMBER
WW-6

Trenching and Excavation Safety

The employer must comply with the trenching and excavation requirements of 29 CFR 1926.651 and 1926.652 or comparable OSHA-approved state plan requirements.

Inspection of Excavations

OSHA standards require that a competent person inspect trenches daily and as conditions change before worker entry to ensure elimination of excavation hazards. A competent person is an individual who is capable of identifying existing and predictable hazards or working conditions that are hazardous, unsanitary, or dangerous to workers, soil types and protective systems required, and who is authorized to take prompt corrective measures to eliminate these hazards and conditions.

Access and Egress

OSHA standards require safe access and egress to all excavations, including ladders, steps, ramps, or other safe means of exit for employees working in trench excavations 4 feet (1.22 meters) or deeper. These devices must be located within 25 feet (7.6 meters) of all workers.

Recommendations

Heavy equipment and trucks should stay as far as possible from the edge of any trench.
Always use pads under stabilizers to minimize ground pressures that could lead to failures.

(b) Definitions

"Cemented soil" means a soil in which the particles are held together by a chemical agent, such as calcium carbonate, such that a hand-size sample cannot be crushed into powder or individual soil particles by finger pressure.

"Cohesive soil" means clay (fine grained soil), or soil with a high clay content, which has cohesive strength. Cohesive soil does not crumble, can be excavated with vertical sideslopes, and is plastic when moist. Cohesive soil is hard to break up when dry, and exhibits significant cohesion when submerged. Cohesive soils include clayey silt, sandy clay, silty clay, clay and organic clay.

"Dry soil" means soil that does not exhibit visible signs of moisture content.

"Fissured" means a soil material that has a tendency to break along definite planes of fracture with little resistance, or a material that exhibits open cracks, such as tension cracks, in an exposed surface.

"Granular soil" means gravel, sand, or silt (coarse grained soil) with little or no clay content. Granular soil has no cohesive strength. Some moist granular soils exhibit apparent cohesion. Granular soil cannot be molded when moist and crumbles easily when dry.

"Layered system" means two or more distinctly different soil or rock types arranged in layers. Micaceous seams or weakened planes in rock or shale are considered layered.

"Moist soil" means a condition in which a soil looks and feels damp. Moist cohesive soil can easily be shaped into a ball and rolled into small diameter threads before crumbling. Moist granular soil that contains some cohesive material will exhibit signs of cohesion between particles.

"Plastic" means a property of a soil which allows the soil to be deformed or molded without cracking, or appreciable volume change.

"Saturated soil" means a soil in which the voids are filled with water. Saturation does not require flow. Saturation, or near saturation, is necessary for the proper use of instruments such as a pocket penetrometer or sheer vane.

"Soil classification system" means, for the purpose of this subpart, a method of categorizing soil and rock deposits in a hierarchy of Stable Rock, Type A, Type B, and Type C, in decreasing order of stability. The categories are determined based on an analysis of the properties and performance characteristics of the deposits and the characteristics of the deposits and the environmental conditions of exposure.

"Stable rock" means natural solid mineral matter that can be excavated with vertical sides and remain intact while exposed.

"Submerged soil" means soil which is underwater or is free seeping.

"Type A" means cohesive soils with an unconfined, compressive strength of 1.5 ton per square foot (tsf) (144 kPa) or greater. Examples of cohesive soils are: clay, silty clay, sandy clay, clay loam and, in some cases, silty clay loam and sandy clay loam. Cemented soils such as caliche and hardpan are also considered Type A.

However, no soil is Type A if:

(i) The soil is fissured; or
(ii) The soil is subject to vibration from heavy traffic, pile driving, or similar effects; or
(iii) The soil has been previously disturbed; or
(iv) The soil is part of a sloped, layered system where the layers dip into the excavation on a slope of four horizontal to one vertical (4H:1V) or greater; or
(v) The material is subject to other factors that would require it to be classified as a less stable material.

"Type B" means:

(i) Cohesive soil with an unconfined compressive strength greater than 0.5 tsf (48 kPa) but less than 1.5 tsf (144 kPa), or
(ii) Granular cohesionless soils including: angular gravel (similar to crushed rock), silt, silt loam, sandy loam and, in some cases, silty clay loam and sandy clay loam.
(iii) Previously disturbed soils except those which would otherwise be classed as Type C soil.
(iv) Soil that meets the unconfined compressive strength or cementation requirements for Type A, but is fissured or subject to vibration; or
(v) Dry rock that is not stable; or
(vi) Material that is part of a sloped, layered system where the layers dip into the excavation on a slope less steep than four horizontal to one vertical (4H:1V), but only if the material would otherwise be classified as Type B.

"Type C" means:

(i) Cohesive soil with an unconfined compressive strength of 0.5 tsf (48 kPa) or less; or
(ii) Granular soils including gravel, sand, and loamy sand; or
(iii) Submerged soil or soil from which water is freely seeping; or
(iv) Submerged rock that is not stable, or
(v) Material in a sloped, layered system where the layers dip into the excavation or a slope of four horizontal to one vertical (4H:1V) or steeper.

"Unconfined compressive strength" means the load per unit area at which a soil will fail in compression. It can be determined by laboratory testing, or estimated in the field using a pocket penetrometer, by thumb penetration tests, and other methods.

"Wet soil" means soil that contains significantly more moisture than moist soil, but in such a range of values that cohesive material will slump or begin to flow when vibrated. Granular material that would exhibit cohesive properties when moist will lose those cohesive properties when wet.

(c) Requirements

(1) Classification of soil and rock deposits. Each soil and rock deposit shall be classified by a competent person as Stable Rock, Type A, Type B, or Type C in accordance with the definitions set forth in paragraph (b) of this appendix.

(2) Basis of classification. The classification of the deposits shall be made based on the results of at least one visual and at least one manual analysis. Such analyses shall be conducted by a competent person using tests described in paragraph (d) below, or in other recognized methods of soil classification and testing such as those adopted by the American Society for Testing Materials, or the U.S. Department of Agriculture textural classification system.

(3) Visual and manual analyses. The visual and manual analyses, such as those noted as being acceptable in paragraph (d) of this appendix, shall be designed and conducted to provide sufficient quantitative and qualitative information as may be necessary to identify properly the properties, factors, and conditions affecting the classification of the deposits.

(4) Layered systems. In a layered system, the system shall be classified in accordance with its weakest layer. However, each layer may be classified individually where a more stable layer lies under a less stable layer.

(5) Reclassification. If, after classifying a deposit, the properties, factors, or conditions affecting its classification change in any way, the changes shall be evaluated by a competent person. The deposit shall be reclassified as necessary to reflect the changed circumstances.

(d) Acceptable visual and manual tests

(1) Visual tests. Visual analysis is conducted to determine qualitative information regarding the excavation site in general, the soil adjacent to the excavation, the soil forming the sides of the open excavation, and the soil taken as samples from excavated material.

(i) Observe samples of soil that are excavated and soil in the sides of the excavation. Estimate the range of particle sizes and the relative amounts of the particle sizes. Soil that is primarily composed of fine-grained material material is cohesive material. Soil composed primarily of coarse-grained sand or gravel is granular material.

(ii) Observe soil as it is excavated. Soil that remains in dumps when excavated is cohesive. Soil that breaks up easily and does not stay in dumps is granular.

(iii) Observe the side of the opened excavation and the surface area adjacent to the excavation. Crack-like openings such as tension cracks could indicate fissured material. If chunks of soil spall off a vertical side, the soil could be fissured. Small spalls are evidence of moving ground and are indications of potentially hazardous situations.

(iv) Observe the area adjacent to the excavation and the excavation itself for evidence of existing utility and other underground structures, and to identify previously disturbed soil.

(v) Observe the opened side of the excavation to identify layered systems. Examine layered systems to identify if the layers slope toward the excavation. Estimate the degree of slope of the layers.

(vi) Observe the area adjacent to the excavation and the sides of the opened excavation for evidence of surface water, water seeping from the sides of the excavation, or the location of the level of the water table.

(vii) Observe the area adjacent to the excavation and the area within the excavation for sources of vibration that may affect the stability of the excavation face.

(2) Manual tests. Manual analysis of soil samples is conducted to determine quantitative as well as qualitative properties of soil and to provide more information in order to classify soil properly.

(i) Plasticity. Mold a moist or wet sample of soil into a ball and attempt to roll it into threads as thin as 1/8-inch in diameter. Cohesive material can be successfully rolled into threads without crumbling. For example, if at least a two inch (50 mm) length of 1/8-inch thread can be held on one end without tearing, the soil is cohesive.

(ii) Dry strength. If the soil is dry and crumbles on its own or with moderate pressure into individual grains or fine powder, it is granular (any combination of gravel, sand, or silt). If the soil is dry and falls into dumps which break up into smaller dumps, but the smaller dumps can only be broken up with difficulty, it may be clay in any combination with gravel, sand or silt. If the dry soil breaks into dumps which do not break up into small dumps and which can only be broken with difficulty, and there is no visual indication the soil is fissured, the soil may be considered unfissured.

(iii) Thumb penetration. The thumb penetration test can be used to estimate the unconfined compressive strength of cohesive soils. (This test is based on the thumb penetration test described in American Society for Testing and Materials (ASTM) Standard designation D2488 - "Standard Recommended Practice for Description of Soils (Visual - Manual Procedure).") Type A soils with an unconfined compressive strength of 1.5 tsf can be readily indented by the thumb; however, they can be penetrated by the thumb only with very great effort. Type C soils with an unconfined compressive strength of 0.5 tsf can be easily penetrated several inches by the thumb, and can be molded by light finger pressure. This test should be conducted on an undisturbed soil sample, such as a large clump of spoil, as soon as practicable after excavation to keep to a minimum the effects of exposure to drying influences.If the excavation is later exposed to wetting influences (rain, flooding), the classification of the soil must be changed accordingly.

(iv) Other strength tests. Estimates of unconfined compressive strength of soils can also be obtained by use of a pocket penetrometer or by using a hand-operated shearvane.

(v) Drying test. The basic purpose of the drying test is to differentiate between cohesive material with fissures, unfissured cohesive material, and granular material. The procedure for the drying test involves drying a sample of soil that is approximately one inch thick (2.54 cm) and six inches (15.24 cm) in diameter until it is thoroughly dry:


(A) If the sample develops cracks as it dries, significant fissures are indicated.

(B) Samples that dry without cracking are to be broken by hand. If considerable force is necessary to break a sample, the soil has significant cohesive material content. The soil can be classified as an unfissured cohesive material and the unconfined compressive strength should be determined.


(C) If a sample breaks easily by hand, it is either a fissured cohesive material or a granular material. To distinguish between the two, pulverize the dried clumps of the sample by hand or by stepping on them. If the clumps do not pulverize easily, the material is cohesive with fissures.If they pulverize easily into very small fragments, the material is granular.

EXCAVATIONS IN TYPE A SOILS


All simple slope excavations 20 feet or less in depth shall have a maximum allowable slope of ¾:1.



Exception: Simple slope excavations which are open 24 hours or less (short term) and which are 12 feet or less in depth shall have a maximum allowable slope of ½:1




All benched excavations 20 feet or less in depth shall have a maximum allowable slope of ¾:1 and maxium bench dimensions as follows:



All excavations 8 feet or less in depth which have unsupported vertically sided lower portions shall have a maximum vertical side of ¾ feet.

All excavations more than 8 feet but not more than 12 feet in depth with unsupported vertically sided lower portions shall have a maximum allowable slope of 1:1 and a maximum vertical side of ¾ feet.


All excavations 20 feet or less in depth which have vertically sided lower portions that are supported or shielded shall have a maximum allowable slope of ¾:1. The support or shield system must extend at least 18 inches above the top of the vertical side.



All other simple slope, compound slope, and vertically sided lower portion excavations shall be in accordance with the other options permitted under § 1926.652(b).


EXCAVATIONS IN TYPE B SOILS

All simple slope excavations 20 feet or less in depth shall have a maximum allowable slope of 1:1.




SIMPLE SLOPE

All benched excavations 20 feet or less in depth shall have a maximum allowable slope of 1:1 and maxium bench dimensions as follows:



All excavations 20 feet or less in depth which have vertically sided lower portions that are supported or shielded shall have a maximum allowable slope of 1:1. The support or shield system must extend at least 18 inches above the top of the vertical side.




VERTICALLY SIDED LOWER PORTION

All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).


EXCAVATIONS IN TYPE C SOILS

All simple slope excavations 20 feet or less in depth shall have a maximum allowable slope of 1½:1.



SIMPLE SLOPE

All excavations 20 feet or less in depth which have vertically sided lower portions that are supported or shielded shall have a maximum allowable slope of 1½:1. The support or shield system must extend at least 18 inches above the top of the vertical side.




VERTICALLY SIDED LOWER PORTION

All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).

EXCAVATIONS IN LAYERED SOILS

All excavations 20 feet or less in depth made in layered soils shall have a maximum allowable slope for each layer as set forth below.



All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).

AWT
Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

RoCo Builders , LLC
RoCo Builders - Homewood Ln

Project Location:
Homewood Ln
Statesville, NC 28625
Iredell County
PIN: 4737895725

Project Owner:
RoCo Builders , LLC
355 Country Ridge Rd
Rockwell, NC 28138
704-468-2301
enewtonsc4@gmail.com

For Review Only

REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE

Excavation Safety

DRAWN BY:	CREATED ON:
D. Harkins	10.31.2024
REVISED BY:	REVISED ON:
RELEASED BY:	RELEASED ON:

DRAWING NUMBER

WW-7

Septic System Design - Summary Page

Engineers and Soil Scientists
Agri-Waste Technology, Inc.

Project Manager:
Jeff Vaughan, PhD, LSS
jvaughan@agriwaste.com
919-859-0669

Daniel Harkins
dharkins@agriwaste.com
828-514-1726

Project: RoCo Builders - Homewood Ln
Property: Homewood Ln
Statesville, NC 28625
Subdiv.:
Lot #:

Owner: RoCo Builders , LLC
Address: 355 Country Ridge Rd
Rockwell, NC 28138
Phone: 704-408-2301
Email: enewtonsc4@gmail.com

EHS:

Date: 3/11/2025
County: Iredell
Permit #:
Type of System: II a
PIN: 4737895725

Soil Parameters

Soil Evaluation By:
Jeff Vaughan, PhD, LSS

Special Conditions/Notes:

LTAR: 0.30 gpd/ft^2

Design Parameters

Type of Establishment: Residence, 5 or fewer bedrooms
Unit: Bedroom
# of Units: 4

Septic Tank Specifications

Min. Tank Capacity: 1,000 gal
Actual Tank Volume: 1,000 gal
Tank Manufacturer: Shoaf
Tank Model: TS 1000 STB

	Exterior	Interior	
Length:	108.0	102.0	in.
Width:	58.0	52.0	in.
Depth:	67.5	60.5	in.

Primary Drainfield Specifications

Type of Distribution: Parallel Distribution Box
Trench Media: Chambers
Trench Width: 3 ft
Trench Depth: in.
(or as specified on permit)

Trench Bottom Area: 1600 ft^2
Minimum Drain Line: 400 ft
Actual Drain Line: 402 ft
Number of Lines: 3
Minimum Line Spacing: 9 ft O.C.

Wastewater Treatment System Design Calculations

Project: RoCo Builders - Homewood Ln
Location: Homewood Ln
Statesville, NC 28625
County: Iredell

Septic Tank Sizing

Daily Flow Estimate:

	Unit	# of Units	Flow/Unit	Flow/Day
1A	Bedroom	4	120	480
2A				
3B				
			Q=	480 gpd

Septic Tank Minimum Capacity: Per 15A NCAC 18E .0801

For individual residences with 4 or fewer bedrooms

Minimum Liquid Capacity (V)= 1,000 gal

Septic Tank Specs:

Manufacturer:	Shoaf	
Model:	TS 1000 STB	
Volume:	1,000	gal
Weight:	10,500	lbs

	Exterior	Interior	
Length:	108.0	102.0	in.
Width:	58.0	52.0	in.
Depth:	67.5	60.5	in.

Shape of Risers: Circular
Diameter: 2.00 ft

Pump Tank Storage & Float Settings

Project: RoCo Builders - Homewood Ln
Location: Homewood Ln
Statesville, NC 28625
County: Iredell

Tank Manufacturer	Shoaf
Tank Model	MS 1250 PT*

Repair System

Elevations, measured from bottom towards top (0 = Interior Bottom of Tank):

Top of pump (including 4" block)	14.1 in.	(Pump height = 10 1/16")
Pump Off	16.0 in.	
Pump On	24.0 in.	(set for dose volume)
Alarm On	30.0 in.	(6 in. above On Float)

Emergency Storage Available	
Pump Tank	610 gal
Days of Storage	1.27 days

(determined from "interior top of tank" - "High Water Alarm")

ELEVATIONS

Project: RoCo Builders - Homewood Ln
Location: Homewood Ln
Statesville, NC 28625
County: Iredell

Benchmark	0	
BM Elev	0 ft	

Septic Tank	1,000 gal	
Ground Surface		819.62 ft
Depth of Soil Cover	12 in.	1.00 ft
Overall Ht of Tank	67.5 in.	5.63 ft
Elev, Base of Tank		813.00 ft
Ht to 4" Inlet Invert	57 in.	4.75 ft
Elev, 4" Inlet Invert		817.75 ft
Ht to 4" Outlet Invert	55 in.	4.58 ft
Elev, 4" Outlet Invert		817.58 ft
Gravel Base	6 in.	0.50 ft
Elev, Bot of Excavation		812.50 ft

ST Inlet Pipe		
Grade @ Stub-out		820.22 ft
Depth of Stub-out, top		1.5 ft
Elev, Stub-out Invert		818.37 ft
Elev @ ST Inlet Invert		817.75 ft
Length		17 ft
Slope		3.7 %

Pipe, ST to PT		
ID	4 in.	0.33 ft
OD	4.5 in.	0.38 ft
Elev, ST Outlet Invert		817.58 ft
Elev, PT Inlet Invert		817.47 ft
Length		3 ft
Slope		3.6 %
Cover over inlet pipe		1.52 ft

Drainfield Design

Project RoCo Builders - Homewood Ln
Location Homewood Ln
Statesville, NC 28625
County Iredell

Drainfield Sizing

Primary

LTAR	0.3 gpd/ft^2		
Daily Design Flow	480 gpd	**Type of Drainfield Media**	Chambers
Req. Drainfield Area	1,600 ft^2	**Required Drainline**	
Trench Width, Eff.	3 ft	**After 25% Reduction**	400 ft
Required Drainline	533 ft	**Minimum Line Spacing**	9 ft (O.C.)

Repair

LTAR	0.3 gpd/ft^2		
Daily Design Flow	480 gpd	**Type of Drainfield Media**	Chambers
Req. Drainfield Area	1,600 ft^2	**Required Drainline**	
Trench Width, Eff.	3 ft	**After 25% Reduction**	400 ft
Required Drainline	533 ft	**Minimum Line Spacing**	9 ft (O.C.)

Drainfield Layout

Line	Use	Color	Elevation	Length	Primary	Repair
1	Layout Line	White		105		98.0
2	Layout Line	Purple		126		98.0
3	Layout Line	Blue		166		102.0
4	Layout Line	White		62		
5	Layout Line	Purple		253		102.0
6	Layout Line	Blue		205	134.0	
7	Layout Line	Purple		156	134.0	
8	Layout Line	White		200	134.0	
9	Layout Line	Purple		74		
10	Layout Line	Blue		52		
11	Layout Line	White		29		
			Total	1428	402	400
			Count	11	3	4

Note: Line length totals are shown to the nearest foot.
For Chambers or Low-profile Chambers:
Effective trench lengths are shown. Add 1' for total installation length.

PRESSURE MANIFOLD SYSTEM DESIGN (Repair)

Site Information

Project: RoCo Builders - Homewood Ln
Location: Homewood Ln
Statesville, NC 28625
County: Iredell

Design Information

Estimated Daily Flow	480	gal/day
L.T.A.R. (from Iredell Co.)	0.3	gal/day/ft^2
L.T.A.R. + 5%	0.315	gal/day/ft^2
Trench Width	3	ft.
Line Length Required	533	ft.
Length after 25% Reduction	400	ft
L.T.A.R. Reduced	0.400	gal/day/ft^2
L.T.A.R. Reduced + 5%	0.420	gal/day/ft^2

DRAINFIELD INFO. - **Repair**

Proposed Type of System/Distribution: ***Pump to Pressure Manifold using Chambers***

Line No.	Flag Color	Line Length (ft.)		Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
1	White	98	1/2in SCH 80	5.48	0.056	0.408
2	Purple	98	1/2in SCH 80	5.48	0.056	0.408
3	Blue	102	1/2in SCH 80	5.48	0.054	0.392
5	Purple	102	1/2in SCH 80	5.48	0.054	0.392
	Total	**400**	**Total**	**21.92**	**Avg.**	**0.40**

Note: Line lengths are calculated in 4' increments to reflect use of Chambers product. 2' added for endcaps.

Total Run Time	21.90	min.	
Drainfield Capacity	261.2	gal	
% of Drainfield Cap	66.8%		(Req. Range 66-75%)
Dose Volume	174.4	gal/dose	
Run Time/Dose	**8.0**	**minutes**	Range 5-7 minutes unless uphill, checked
Volume/depth	21.80	gal/in.	(Per tank manufacturer's specifications)
Estimated Drawdown	8.00	in.	

Manifold Box

Number of Taps	4	with	0	Split(s)	
Manifold Length	3.5	ft.	(approximate)		

PUMP DESIGN

System (initial/repair): **Repair**

Project: RoCo Builders - Homewood Ln
Location: Homewood Ln
Statesville, NC 28625
County: Iredell

Friction Losses

Suction Head	0 ft		*(submersible 0)*
Elev. Difference (highest point from pump)	6.09 ft		
Design Pressure At Outlet	2 ft		

Supply Line - 2" Schedule 40 PVC

Pipe Diameter, Nominal	2 in.			
Pipe Diameter (ID)	2.047 in.	Flow	21.92 gpm	
Pipe Length	57 ft	Velocity	2.14 ft/s	
Pipe Length for Fittings	5.7 ft		Meets requirement that 2 ft/s < v < 5 ft/s.	
Equivalent Length	62.7 ft			
Estimated Friction Loss in Supply Line	0.57 ft			
Pressure Filter Friction Loss	0.23 ft			*(from manufacturer)*
Friction Loss - Taps/Special Fittings	3.5 ft			
TOTAL	**12.39 ft.**			

Flow for Anti-Siphon Hole


Hole Diameter	3/16 in.
Hole Flowrate	1.46 gpm

Pump Efficiency	0.7	*(assumed, typical)*
Motor Efficiency	0.9	*(assumed for electric pumps)*
Flow	**23.38 gpm**	

Required Horsepower	0.12 hp
TDH	**12.39 ft.**

Pump Selection

Manufacturer:	Zoeller
Model:	N53
Horsepower:	**0.3**



Attachment 2: Soil Boring Description Sheets

501 N Salem St, Suite 203
Apex, NC 27502

919.859.0669
agriwaste.com

Engineers and Soil Scientists

SOIL/SITE EVALUATION *for* ON-SITE WASTEWATER SYSTEM

OWNER: RoCo Builders LLC APPLICATION DATE: _____
ADDRESS: 113 Homewood Lane, Statesville, NC, 28625 EVALUATION DATE: 10/30/24
PROPERTY ID: 4737895725 COUNTY: Iredell
PROPOSED FACILITY: Single Family Residence PROPOSED DESIGN FLOW (.0400): 480 GPD PROPERTY SIZE: ~ 1.5 ac.
LOCATION OF SITE: 113 Homewood Lane, Statesville, NC, 28625 PROPERTY RECORDED: _____
WATER SUPPLY: ☑ Public ☐ Single Family Well ☐ Shared Well ☐ Spring ☐ Other _____ WATER SUPPLY SETBACK: 10 ft.
EVALUATION METHOD: ☑ Auger Boring ☐ Pit ☐ Cut TYPE OF WASTEWATER: ☑ Domestic ☐ High Strength ☐ IPWW

PROFILE #	.0502 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY .0503 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY .0503 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .0504 SOIL WETNESS/ COLOR	.0505 SOIL DEPTH	.0506 SAPRO CLASS	.0507 RESTR HORIZ	.0509 PROFILE CLASS & LTAR*	.0502(d) SLOPE CORRECTION
SB 1	8%	0-10"	SCL; GR	SS; SP; FR	-	48"	-	-	0.3 GPD/Ft2	45"
		10-30"	C; SBK	SS; SP; FI						
		30-48"	CL; WSBK	SS; SP; FR						
SB 2	8%	0-6"	SCL; GR	SS; SP; FR	-	48"	-	-	0.3 GPD/Ft2	45"
		6-42"	C; SBK	SS; SP; FI						
		42-48"	CL; WSBK	SS; SP; FR						
SB 3	6%	0-6"	SCL; GR	SS; SP; FR	-	45"	-	Saprolite	0.3 GPD/Ft2	43"
		6-28"	C; SBK	SS; SP; FI						
		28-45"	CL; WSBK	SS; SP; FR						
		45+"	SCL; MA	SS; SP; FR						
SB 4	5%	0-8"	SCL; GR	SS; SP; FR	-	48"	-	-	0.3 GPD/Ft2	46"
		8-32"	C; SBK	SS; SP; FI						
		32-48"	CL; WSBK	SS; SP; FR						

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.0508)	Suitable	Suitable
System Type(s)	Type IIb, gravity to 25% reduction drain field product	Type IIIb, pump to 25% reduction drain field product
Site LTAR	0.3 GPD/Ft^2	0.3 GPD/Ft^2
Maximum Trench Depth	31"	31"

SITE CLASSIFICATION (.0509): _____
EVALUATED BY: Trevor Hackney
OTHER(S) PRESENT: Nathan Estevez

Comments: _____

LEGEND

LANDSCAPE POSITION	SOIL GROUP	SOIL TEXTURE	CONVENTIONAL LTAR (gpd/ft²)	SAPROLITE LTAR (gpd/ft²)	LPP LTAR (gpd/ft²)	MINERALOGY/ CONSISTENCE		STRUCTURE
CC (Concave slope)	I	S (Sand)	0.8 - 1.2	0.6 - 0.8	0.4 -0.6	MOIST	WET	SG (Single grain)
CV (Convex Slope)		LS (Loamy sand)		0.5 -0.7		Lo (Loose)	NS (Non-sticky)	M (Massive)
D (Drainage way)	II	SL (Sandy loam)	0.6 - 0.8	0.4 -0.6	0.3 - 0.4	VFR (Very friable)	SS (Slightly sticky)	GR (Granular)
FP (Flood plain)		L (Loam)		0.2 - 0.4		FR (Friable)	S (Sticky)	SBK (Subangular blocky)
FS (Foot slope)	III	SiL (Silt loam)	0.3 - 0.6	0.1 - 0.3	0.15 - 0.3	FI (Firm)	VS (Very sticky)	ABK (Angular blocky)
H (Head slope)		SCL (Sandy clay loam)		0.05 - 0.15**		VFI (Very firm)	NP (Non-plastic)	PR (Prismatic)
L (Linear Slope)		CL (Clay loam)		None		EFI (Extremely firm)	SP (Slightly plastic)	PL (Platy)
N (Nose slope)		SiCL (Silty clay loam)					P (Plastic)	
R (Ridge/summit)		Si (Silt)					VP (Very plastic)	
S (Shoulder slope)	IV	SC (Sandy clay)	0.1 - 0.4		0.05 - 0.2	SEXP (Slightly expansive)		
T (Terrace)		SiC (Silty clay)				EXP (Expansive)		
TS (Toe Slope)		C (Clay)						
		O (Organic)	None					

* Adjust LTAR due to depth, consistence, structure, soil wetness, landscape, position, wastewater flow and quality.
**Sandy clay loam saprolite can only be used with advanced pretreatment in accordance with 15A NCAC 18E .1200.

HORIZON DEPTH In inches below natural soil surface
DEPTH OF FILL In inches from land surface
RESTRICTIVE HORIZON Thickness and depth from land surface
SAPROLITE S(suitable) or U(unsuitable); Evaluation of saprolite shall be by pits.
SOIL WETNESS Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation
CLASSIFICATION S (Suitable) or U (Unsuitable)

Show profile locations and other site features (dimensions, reference or benchmark, and North).

