IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625 PERMIT # 232937

SEPTIC IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4748313151

APPLICANT/OWNER: Refuge Church APPLICANT ADDRESS: P.O. Box 6045 Statesville NC 28687

SITE ADDRESS: 773 Jennings Rd Statesville NC 28625 PHONE: 980-273-9800 ALT. PHONE N/A

SITE DIRECTIONS: I77 T/L Jennings, Cross I77, Pass Deerhaven Gravel drive SAP CONTROLLED: ☐ YES ☒ NO

SUBDIVISION: Seaboard Farm + Forestry LLC SECTION: N/A LOT # 1 LOT AREA: 7ac DESIGN FLOW: 384gpd L.T.A.R.: 0.3

Septic Tank	1000	(gal)	STB 760	Date 2-22	☒ New System	☐ Repair	☐ Expansion	System Type: I II III IV V VI	☐ Residence	No. Bedrooms		Water Supply
Pump Tank		(gal)	PT	Date	System Description: 25% reduction				☐ Business	No. Persons	128	☒ Private
Pump Make		Model		Serial #	Repair System Description: 25% reduction				☒ Other	No. Employees		☐ Public
# Nitrification Fields	1	# Lines		Linear Ft 322	Maintenance Agreement Required:	☐ YES	☒ NO		☒ Slab	☐ Crawl Space		☐ Community
Trench Width	36"	Trench Bottom Depth(Low side)		Gravel Depth		☒ GRAVITY	☐ PRESSURE		☐ Basement w/plumbing		☐ Basement w/o plumbing	


Comments / Conditions: See plan by CS+SC

Plan approved for 128 seats with no kitchen and no daycare facility

INITIAL SITE SKETCH

See plan by CS+SC

AS BUILT SKETCH



Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. **CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION**

☐ **IMPROVEMENT PERMIT** *with plat valid without expiration.* ☒ **IMPROVEMENT PERMIT** *with site plan valid for 60 mos.* ☒ **AUTHORIZATION TO CONSTRUCT** *valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.*

Owner / Applicant Signature: Brett Rice Date: 02/15/18 Installed by: Ground Breakers (Shannon H)

IMPROVEMENT PERMIT by: Date: 02/01/18 OPERATION PERMIT by: Patrick D Boyce III Date: 04/16/2019

AUTHORIZATION TO CONSTRUCT by: Date: 02/01/18 Existing System Inspected by: Date:

FOR SEPTIC FINAL INSPECTION: CALL 704-664-3703 between 8am-9am the day the inspection is needed. Be sure to speak with an inpsector to confirm your inspection time.

SERVED R/W
ESS AND UTILITIES

60.0'

EXISTING GRAVEL DRIVE TO BE REMOVED

LOT 1
7.000 ACRES

26" WHITE OAK

28" WHITE OAK

40" RED OAK

CONCRETE WALK ADA ACCESSIBLE

138.9'

REFUGE CHURCH

60'

60'

CONCRETE

5 SPACES

24'

26'

14 SPACES

TYP. 9' x 19'

48'

GRAVEL PARKING

24 SPACES

24' GRAVEL DRIVE

SCALE: 1" = 60'

60 0 60 120

EX 1/2" PIPE

46.12'

(218.95') N74°58'21"E

FENCE

15' SIDE SETBACK

NATURAL WOODED BUFFER TO REMAIN

S83°26'13"W

(226.85')

662.74' TOTAL

EIP

(16.93')

EIP

GRAVEL DRIVE

PP

(202.91')

282.3'

P5

1 R 106'

2 O 106'

3 Y 110'

P1

4 B 39'

5 P 140'

6 R 145'

7 O 165'

P2

35' FRONT SETBACK

20' HARD SURFACE ENTRY

24' RADIUS

60' 18' CMP

0.347 ACRE IN ROAD R/W

S15°51'49"E

462.69

PP

JENNINGS ROAD

SR# 1892 - 60' PUBLIC R/W

TIE LINE
N24°23'58"E
397.94'

EIP

(32.06')

PP

PB 42-123

1

Carolina Soil & Septic Consulting, PLLC

P.O. Box 1703, Mooresville, NC 28115

Phone: (704) 202-5791 Email: adrianpruett@yahoo.com

NC Licensed Soil Scientist, SC Professional Soil Classifier,
Certified Septic System Operator, Licensed Septic Installer,
Certified Septic Inspector

Proposed Design for a 25% Reduction Septic System using Gravity distribution for Refuge Church with a 128 seat capacity on 7.0 acres on Jennings Rd., PIN# 4748313151 Statesville, Iredell County, North Carolina.

Contents: **Page**

Information for the Installer---------- 1

Design Information
Design Specifications---------- 2
Layout Specifications---------- 3

Site Plan/System Plan---------- 4

Dosing Calculations---------- 5

Soil Profile Descriptions---------- 6-7

Floor Plan---------- 8

January 25, 2018
Project #: 17147
Design By: Adrian L. Pruett



INFORMATION FOR INSTALLER:

- The permit should be read very carefully prior to submitting bid. The following are details that must be considered along with all other considerations.
- Tanks shall be approved by NC DHHS, and certification supplied by the manufacturer.
- All tanks shall be properly back filled and compacted to prevent slump at a later date.
- The installer is responsible for final grades and returning that grade to original, with exception of added structural features.
- The supply trench shall be compacted to eliminate any cavities left during initial fill placement.
- Installation of the system shall be during dry conditions in order to protect the soil structure.
- All fittings shall be pressure rated fittings.
- All joints shall be cleaned with PVC pipe cleaner and a heavy bodied glue applied to weld all joints.
- Where required by the county health department, post installation inspections by the designer must be scheduled 5 week days in advance.
- Trenches shall be carefully excavated so the bottom has no more than 1/4"fall in 10 feet with no high or low areas within. If high or low areas do exist after trench excavation, high areas should be removed rather than filling in low areas. Do not over excavate trenches! Any fine grading should be completed by hand with a rake and shovel, leaving no loose material.
- All pipe openings in the tanks shall be properly grouted. This also applies to the joints around the riser.
- Earth dams, constructed of relatively impervious material, shall be installed at the beginning and end of each lateral to prevent unwanted lateral water movement.
- Elevations at pin flag locations should be checked by the installer prior to beginning trenches to insure accuracy.
- If septic tank risers are used they should be a minimum of 6" above finished grade or within 6" of final grade if buried.
- Design precludes use of foundation drains on the residence.
- System is specified as an Accepted 25% Reduction Gravity installation.
- Repair is specified as Gravity 25% Reduction installation.
- Trench width is specified as 36" wide, rake and lime all trench sidewalls
- **If grading for slab foundation is utilized do not grade/create greater than 2 ft of elevation difference within 15 ft of any component of the septic or repair.**
- **If back filling do not backfill over any initial or repair septic line.**

REFUGE CHURCH, JENNINGS RD., PIN 4748313151
FIELD LAYOUT SPECIFICATIONS

LAYOUT FOR 128 SEAT CAPACITY CHURCH

January 25, 2018

LINE #	FLAG COLOR	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM			NA		
HOUSE CRN		NA	NA		
P. TANK		NA	NA		
1	***RED***	***NA***	***NA***	***110***	***106***
2	***ORANGE***	***NA***	***NA***	***110***	***106***
3	***YELLOW***	***NA***	***NA***	***113***	***110***
4	BLUE	NA	NA	39	39
5	PINK	NA	NA	140	140
6	RED	NA	NA	145	145
7	ORANGE	NA	NA	155	155
			Total	**812**	**801**

	LINE LENGTH	SYSTEM TYPE	SOIL LTAR GPD/FT^2	TRENCH SYSTEM	DISTRIBUTION
System	***322***	***ACCEPT.***	***0.300***	***25% RED.***	***GRAVITY***
Repair	479	*ACCEPT.*	0.275	25% RED.	GRAVITY

Notes: ** TBM Is Not Required.
**All measures in feet
**Nitrification lines are demonstrated on contour via colored pin flags

Comments: **Church gallons per day flow is based off of 3 gallons per person times 128 members.**
Chruch contains no kitchen or daycare facilities.
All infield laid out septic lines were survey located.
Iredell County has CS&SC's permission to change septic tank location and distribution type

OWNER INFORMATION

Owner:	Refuge Church
Address:	PO Box 6045 Statesville, NC 28687
Contact:	Gene Shumaker
Phone:	980-223-9800
County:	Iredell
Location:	REFUGE CHURCH, JENNINGS RD., PIN 4748313151
Source of Wastewater Flow:	128 SEAT CAPACITY CHURCH
Estimated Gallons Per Day Flow:	384
System Flow:	NA

25% GRAVITY DESIGN INFORMATION

Drainfield Design Flow (gpd):	322
Loading/Soil Application Rate (gpd/ft.^{2}):	0.300
Depth of Gravel in Trench:	NA (25% reduction)
Gravel Size:	NA (25% reduction)
Total Lateral Length From Layout:	322
Total Lateral Length Required:	320
Trench Depth:	31 in. Lowside
Trench Width:	36 in.
TOTAL AREA TRENCH BOTTOM:	966
Trench Spacing on Center:	9 ft.
Repair Trench Spacing:	9 ft.
Repair Trench Depth:	31 in.
Septic Tank Size:	1000 gal.
Estimated Supply Line Length:	242
Supply Line Diameter:	3 in. SCH 40 PVC
Supply Line Volume:	87.12
Dosing Volume:	NA
Supply Manifold:	SERIAL DISTRIBUTION OR DISTRIBUTION BOX
Additional Comments:	Soil suitability was performed by Adrian L. Pruett LSS

DOSING CALCULATIONS

Location Jennings Rd
PIN#: 4748313151
Address: Jennings Rd

No. of Members	128
Design Flow	384 $^{gal}/_{day}$
LTAR	0.300 $^{gal}/_{ft^2\ day}$
25% RED. Expansion? (YES OR NO)	YES
Supply Line Length	242 ft.
Supply Line Volume	87.12 gal.
Required Feet of 25% RED. Line	320 ft.
Amount of Line from Layout	322 ft.
Gallons per Minute	NA $^{gal}/_{min}$
Septic Tank Capacity	1000 gal.
Minimum Septic Tank Capacity	1000 gal.
Lateral Line Volume	210.266 gal.

PROPERTY ID #: 4748313151
COUNTY: Iredell

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM
(Complete all fields in full)

OWNER: Refuge Church
ADDRESS: PO Box 6045, Statesville, NC 28687
PROPOSED FACILITY: Church
PROPOSED DESIGN FLOW (.1949): 384 gpd
LOCATION OF SITE: Jennings Rd., Statesville, NC
APPLICATION DATE
DATE EVALUATED: 10/31/17
PROPERTY SIZE: 7.0 ac
PROPERTY RECORDED: Yes

WATER SUPPLY: X Private ☐ Public ☐ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring X Pit ☐ Cut
TYPE OF WASTEWATER: X Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
P 1	LSS 10%	0-5	BR C MFSBK	FR SS SP SEXP	N/A	72"	N/A	N/A	PS
		5-16	R C MFABK	FI S P SEXP					
		16-37	R C WFSBK	FR SS SP SEXP	-FEW SAP				
		37-72	R CL WFSBK	FR SS SP SEXP	-COM SAP				
									0.3 GPD/SQFT
P 2	LSS 14%	0-8	B C MFSBK	FR SS SP SEXP	N/A	73"	N/A	N/A	PS
		8-49	R C MFSBK	FI S P SEXP	-FEW QUARTZ				
		49-73	R CL WFSBK	FR SS SP SEXP	-FEW SAP				
									0.3 GPD/SQFT
P 3	LSS 12%	0-13	B CL WFSBK	FR SS SP SEXP	N/A	57"	N/A	N/A	PS
		13-45	R C MMSBK	FI S P SEXP	-COM MN				
		45-57	R C MFSBK	FI S P SEXP	-FEW/COM MN, FEW YB				0.275 GPD/SQFT TO 45"
									0.25 GPD/SQFT 45 TO 57"
P 4	LSS 10%	0-6	B CL WFSBK	FR SS SP SEXP	N/A	62"	N/A	N/A	PS
		6-28	R C MFSBK/ABK	FI S P SEXP					
		28-62	R C WFSBK	FR SS SP SEXP					
									0.3 GPD/SQFT

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)	GRAVITY 25%	GRAVITY 25%
Site LTAR	0.3	0.275

OTHER FACTORS (.1946): NONE
SITE CLASSIFICATION (.1948): PS
EVALUATED BY: ADRIAN L. PRUETT
OTHER(S) PRESENT:

COMMENTS: SOIL WAS EVALUATED DURING DRY CONDITIONS

SOIL/SITE EVALUATION

(Continuation Sheet-Complete all field in full)

PROPERTY ID #: 4748313151
DATE OF EVALUATION: 10/31/17
COUNTY: IREDELL

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
P 5	LSS 12%	0-13	B SCL/CL WFSBK	FR SS SP SEXP	N/A	63"	N/A	N/A	PS
		13-46	R C MFSBK	FI S P SEXP					
		46-63	R C WFSBK	FR SS SP SEXP	-FEW SAP				0.3 GPD/SQFT

RECEIVED JAN 2 6 2018

IREDELL COUNTY DEPARTMENT of ENVIRONMENTAL HEALTH

APPLICATION FORM

Paid $350.00 # 232937

Application For: ( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment
(X) Septic Improvement Permit (X) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED. APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: (X) Survey Plat, scaled no more than 1 inch = 60 feet
Place an (X) beside whichever is submitted if applicable (X) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information: **(PRINT CLEARLY)**

Applicant Name: Refuge Church/CS&SC **Address:** PO Box 6045, Statesville, NC **Zip:** 28687

Applicant Email: pastor@refugechurchiredell.org **Phone:** 980-223-9800 Gene Shumaker **Alt. Phone:** _____

Owner Name: Same **Address:** _____ **Zip:** _____

Owner Email: _____ **Phone:** _____ **Alt. Phone:** _____

Property Information:

Street Address: 743 Jennings Rd

Subdivision Name: Seaboard Farm & Forestry LLC **Section/Phase:** _____ **Lot Number:** 1

Driving Directions: Hwy 21 N, TL on Jennings, Cross I77, Pass Deer Haven Dr on Left, Gravel drive right past/beside 753 Jennings

Site Development Information: ***(check or complete ALL that apply***

CHECK FOUNDATION TYPE

( ) New Single Family Residence
( ) New Multi-Family Residence
( ) Accessory Building
( ) Bedroom(s) Addition
( ) Repair to failing septic system ___ Tank ___ Drain lines **Describe Problem:** _____

Maximum Number of Bedrooms: _____
Maximum Number of Occupants: _____
( ) Swimming Pool
( ) Other Addition/Structure: _____

( ) Crawl Space Foundation
(X) Concrete Slab Foundation
( ) Basement with Plumbing
( ) Basement without Plumbing

Non-Residential Site Development: **Type of Business:** CHRUCH
Square Footage of Building: 4796 SQFT **Max. Number of Employees:** _____ **Max. Number of Seats/Beds/Other:** 128

Water Supply: ( ) Replacement Well – Reason: _____
( ) Multi-connection Well **Number of Houses:** _____ **Number of Persons:** _____

( ) New Well (X) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: ***(you may rank in order of preference)*** **Year existing system installed:** _____
( ) No Preference (X) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional ( ) Other: _____

Please answer the following to the best of your ability:

( ) Yes (X) No **Does the site contain any jurisdictional wetlands?**
( ) Yes (X) No **Is any non-domestic sewage (i.e. industrial) to be generated?**
( ) Yes (X) No **Is the site subject to approval by any other public agency?**

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: _____ 1-25-18
Property owner or owner's legal representative signature (SIGNATURE REQUIRED) **DATE**

Public Health
Prevent. Promote. Protect.
Iredell County Health Department

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

Public Health
Prevent. Promote. Protect.
Iredell County Health Department

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative:

Power of Attorney; Real Estate Contract; Estate executor; Bankruptcy trustee; Court ordered guardianship

In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:

Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form.

If there are multiple property owners, then all property owners must sign the form that designates a legal representative.

By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department.

I, Gene Shumaker, am the legal owner(s) of the property located at Jennings Rd, Statesville, identified as PIN (Parcel Identification Number) 4748313151, located in Iredell County, North Carolina.

I do hereby authorize (**print legal representative/company name**) Refuge Church, Samuel Shumaker, CS&SC, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.

Samuel E. Shumaker Jr. (dotloop verified 12/05/17 10:14AM EST USNQ-UEFF-JYJF-BU4Y)	12/05/2017	Brett Harig (dotloop verified 12/05/17 10:01AM EST 9RAR-LWPE-W836-NXR)	12/05/2017
Signature of Owner(s)	Date	Signature of Witness	Date

Please return this signed form to the appropriate office:

Mooresville - Environmental Health
ronda.hart@co.iredell.nc.us
Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115

Statesville - Environmental Health
adrienne.shea@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677


IREDELL COUNTY DEPARTMENT of ENVIRONMENTAL HEALTH

SITE PLAN WORKSHEET

SEE THE "SAMPLE SITE PLAN" BELOW. ***INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM OR WELL PERMIT!!!***

Place an (X) beside each item as you complete the site plan:

- (X) Property Line measurements are clearly identified
- (X) All proposed structures are indicated
- (X) Front and side setbacks from property line
- (X) Preferred driveway location
- (X) Preferred well location
- (X) Preferred septic system location
- (X) North arrow, or other sufficient indicator of direction



Circle N/A on the following if appropriate:

- Location of septic systems and wells within 100' of your property **N/A**
- Location of easements and rights of ways on your property **N/A**
- Location of any designated wetlands on the property **N/A**

USE THIS SPACE TO DRAW YOUR SITE PLAN

Show: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site

SEE ATTACHED SITE PLAN AND DESIGN

Signature: _____


Property owner or owner's legal representative signature (SIGNATURE REQUIRED)

1-25-18


DATE

LOT 1
7.000 ACRES
REFUGE CHURCH
30'
70'
CONCRETE WALK ADA ACCESSIBLE
CONCRETE
20'
24'
136.8'
40" RED OAK
28" WHITE OAK
28" WHITE OAK
EXISTING GRAVEL DRIVE TO BE REMOVED
SERVED R/W
ESS AND UTILITIES
60.0'
GRAVEL PARKING
SP ACES
14
24
48'
18' TYP
SCALE: 1" = 60'
60
0
60
120
EX 1/2" PIPE
FENCE
15' SIDE SETBACK
(218.95')
N74°58'21"E
NATURAL WOODED BUFFER TO REMAIN
24' GRAVEL DRIVE
S83°26'13"W
662.74' TOTAL
(226.85')
EIP
(16.93')
EIP
GRAVEL DRIVE
PP
(202.91')
1
EIP
(32.06')
PP
TIE LINE
N24°23'58"E
307.94'
JENNINGS ROAD
SR# 1892 - 60' PUBLIC R/W
S15°51'49"E
462.89'
0.347 ACRE IN ROAD R/W
35' FRONT SETBACK
24' RADIUS
20' HARD SURFACE ENTRY
60'
18' CAP
PP
282.5'
P5
1 R 106'
2 O 106'
3 Y 110'
4 B 99'
5 P 140'
6 R 145'
7 O 155'
P1
P2
R
O
Y
B
P

PB 42-123




1 A2 LIFE SAFETY PLAN
3/16"=1'-0"




2 A2 REFLECTED CEILING PLAN
3/32"=1'-0"


Acknowledgement Of Plans Submittal ONLY!
Date
Date 02/01/18




3 A2 ROOF PLAN
3/32"=1'-0"



4 A2 LAY-IN FIXTURE DETAIL
NO SCALE



5 A2 LAY-IN DIFFUSER DETAIL
NO SCALE



6 A2 LAY-IN FIXTURE DETAIL
NO SCALE

PROPOSED MULTI-USE BUILDING FOR:
REFUGE CHURCH
768 JENNINGS ROAD
STATESVILLE, NC

LIFE SAFETY PLAN, REFLECTED CEILING PLAN, & ROOF PLAN

O'BRIEN ARCHITECTURE
MATTHEW O'BRIEN, ARCHITECT
143 NORTH MAIN STREET
KERNERSVILLE, NORTH CAROLINA 27284
EMAIL: OBRIEN@OBAIA.COM
TELEPHONE: 336.423.4411

COMM. NO.
DATE: 11-6-2017
REVISIONS:

SHEET NO.
A.2

IREDELL COUNTY

PO Box 788
349 North Center St.
Statesville, NC 28677

APPLICATION NUMBER
232937
Issue Date: 01/29/2018

Permit Type: ZONING-IREDELL COUNTY

Parcel Number	Street Address	Jurisdiction
4748313151.000	773 JENNINGS ROAD	

Owner Information	Applicant Information	Contractor Information
Owner: REFUGE CHURCH OF IREDELL INC Address: PO BOX 6045 STATESVILLE, NC 28687 Phone: - -	Applicant: REFUGE CHURCH OF IREDE Address: PO BOX 6045 STATESVILLE, NC 28687 Phone: - -	Contractor: REFUGE CHURCH OF IREDE Address: PO BOX 6045 STATESVILLE, NC 28687 Phone: License Type License Number

Project Description

IREDELL NEW COMMERCIAL

Scope of Work

REFUGE CHURCH OF IREDELL

Permit Details:

IREDELL COUNTY SITE PLAN	Amount:	100.00
TECHNOLOGY FEE - PLANNING	Amount:	2.25
IREDELL COUNTY ZONING	Amount:	75.00
	Amount:	
	Amount:	
	Amount:	
	Amount:	

A ZONING FINAL INPSECTION IS REQUIRED BEFORE A CO INSPECTION CAN BE MADE; ALL PARKING AND LANDSCAPING MUST BE INSTALLED FOR THE ZONING FINAL; ANY CHANGES TO THE SITE PLAN MUST BE SUBMITTED AND APPROVED PRIOR TO BEGINNING WORK

I hereby certify that all information in this application is correct and all work will comply with the state code and all other applicable state and local laws, ordinances and regulations. The respective department will be notified of any changes in the approved plans, a change of contractor, and/or specifications for the project permitted herein. This application becomes a permit only when validated and approved.

Signature of Owner/Contractor

Date: 01/29/2018

ANY PERMIT ISSUED EXPIRES SIX (6) MONTHS AFTER ISSUANCE IF NO INSPECTIONS HAVE BEEN MADE. ANY PERMIT ISSUED SHALL EXPIRE TWELVE (12) MONTHS AFTER LAST INSPECTION IF THE WORK IS DISCONTINUED.

Permit Number	126902	TOTAL FEES:	$ 177.25