Lot 1 GA Mills Plantation Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.225**
Total Ft. Line	535
No. Lines	5 (See Table)
Pump Required	No
Distribution Device	Drop Boxes
Maintenance Agreement Required	No
Repair System	**LP PPBPS**
Total Ft. Line	403
Repair System Loading Rate	0.225

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	Repair	Pink	25% Reduction	57
2	System	Blue	25% Reduction	80 endfed
3	System	White	25% Reduction	95 endfed
4	System	Red	25% Reduction	100 endfed
5	System	White	25% Reduction	130 endfed
6	System	Orange	25% Reduction	130 endfed
7	Repair	Pink	LP PPBPS	185
8	Repair	Blue	LP PPBPS	86
9	Repair		LP PPBPS	75
				Total System: 535'
				Total Repair: 403'

Tank	Red	1000 gal (2 compartment)
House	Blue	

Notes: **Additional Repair located at back of lot.**