Lot 41 GA Mills Plantation Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.3**
Total Ft. Line	400
No. Lines	5 (See Table)
Pump Required	No
Distribution Device	Distribution Box
Maintenance Agreement Required	No
Repair System	**LP PPBPS**
Total Ft. Line	273+
Repair System Loading Rate	0.3

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	Repair	Blue	LP PPBPS	90
2	Repair	Pink	LP PPBPS	90
3	Repair	White	LP PPBPS	93
4	System	Orange	25% Reduction	80 endfed
5	System	Red	25% Reduction	80 endfed
6	System	Blue	25% Reduction	80 endfed
7	System	Pink	25% Reduction	80 endfed
8	System	White	25% Reduction	80 endfed
				Total System: 400'
				Total Repair: 273'

Tank	Red	1000 gal (2 compartment)
House	Blue	

Notes: **Shave off all berms.**