Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)	Elevation (Ft.)
1	System	Blue	25% Reduction	134 endfed	848
2	System	Pink	25% Reduction	134 endfed	
3	System	Red	25% Reduction	134 endfed	
4	Repair	Pink	LPPPBPS	44	
5	Repair	Blue	LPPPBPS	32	
6	Repair	White	LPPPBPS	102	
7	Repair	Orange	LPPPBPS	68	
8	Repair	Pink	LPPPBPS	51	841.7
				Total System: 402'	
				Total Repair: 297'	

Tank	Red	1000 gal (2 compartment)	852.0
Pump Tank	Red	1000 gal.	852.0
House	Pink	Left Rear	852.0

Manifold Information	
Tap Size (In.)	1/2
Tap Material	SCH 80 PVC
No. Taps	3
Barrel Size (In.)	4
Barrel Material	SCH 80 PVC
Flow (gpm)/Tap	5.5

Note: Fill all minor gullies in septic area. Improve drainage from culvert as shown on map
Septic area located on SFE 33-A
Elevations to be verified by surveyor before installation
Well must be drilled according to location shown on map