Lot 63 GA Mills Plantation Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.3**
Total Ft. Line	402
No. Lines	3 (See Table)
Pump Required	No
Distribution Device	Distribution Box
Maintenance Agreement Required	No
Repair System	**25% Reduction**
Total Ft. Line	402+
Repair System Loading Rate	0.3

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	Repair	Orange	25% Reduction	44
2	Repair	Blue	25% Reduction	55
3	Repair	Pink	25% Reduction	78
4	Repair	Orange	25% Reduction	98
5	Repair	White	25% Reduction	127
6	System	Red	25% Reduction	134 endfed
7	System	Blue	25% Reduction	134 endfed
8	System	White	25% Reduction	134 endfed
				Total System: 402'
				Total Repair: 402'

Tank	Red	1000 gal (2 compartment)
House	Blue	

Notes: **Additional Repair located downslope of system.**