IREDELL COUNTY HEATLH DEPARTMENT

PAGE 2: *SITE PLAN WORKSHEET*

SEE THE SAMPLE SITE PLAN BELOW. INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!

Place an (X) beside each item as you complete the site plan:

- ✓ Property Line measurements are clearly identified…
- ✓ All proposed structures are indicated…
  SHOW: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site
- ✓ Front and side setbacks from property line…
- ✓ Preferred driveway location and configuration, preferred well location…
- ✓ Area you prefer your septic system to be placed…
- ✓ North arrow, or other sufficient indicator of direction…

Circle N/A on the following if appropriate:


- ✓ Location of septic systems and wells within 100' of your property… N/A
- ✓ Location of easements and rights of ways on your property… N/A
- ✓ Location of any designated wetlands on the property… N/A

Signature: S & EC, PA (Agent for Applicant)
Property owner or owner's legal representative signature (SIGNATURE REQUIRED)

9/11/08
DATE

USE THIS SPACE TO DRAW YOUR SITE PLAN

See attached site plan



S&EC

Soil & Environmental Consultants, PA

248 LePhillip Court • Concord, North Carolina 28025 • Phone: (704) 720-9405 • Fax: (704) 720-9406
www.SandEC.com

Attached is a proposed design for a Pressure Manifold Septic System for a 3 bedroom single family residence on lot 18 Wheatfield in Iredell County, North Carolina.

Contents: **Page**

Information for the Installer---------- 1

Design Information
- Design Specifications---------- 2-3
- Layout Specifications---------- 4
- System Tapsheet---------- 5
- Repair Tapsheet---------- 6

Site Plan/System Plan---------- 7

Septic Tank Diagram---------- 8

Pump Tank Diagram---------- 9

Pressure Manifold Diagram---------- 10

Control Panel Specifications---------- 11-14

Pump Specifications---------- 15-16

Electric Box Diagram---------- 17

Calculations---------- 18

Maintenance---------- 19-21


August 24, 2008
S & EC Project No. 5-1862
Design By: E. Bailey

Greensboro Office:
3817-E Lawndale Drive
Greensboro, NC 27455
Phone: (336) 540-8234
Fax: (336) 540-8235

Raleigh Office:
11010 Raven Ridge Road
Raleigh, NC 27614
Phone: (919) 846-5900
Fax: (919) 846-9467

INFORMATION FOR THE INSTALLER:

- The permit should be read very carefully prior to bidding. The following are details that must be considered along with all other considerations.
- Tanks shall be approved by DEHNR, and certification supplied by the manufacturer.
- Tanks shall be water tested prior to installation.
- The installer shall be responsible to the owner for placement of the tanks and to insure that final grades are returned to the original natural grade, with exception of added structural features.
- The supply trench shall be compacted to eliminate cavities left during initial fill placement.
- Installation of the system shall be during dry conditions in order to protect the soil structure.
- All fittings shall be pressure rated fittings.
- All joints shall be cleaned with PVC pipe cleaner and a heavy bodied glue applied to weld all joints.
- Where required by the county health department, post installation inspections by the designer must be scheduled 5 week days in advance.
- Trenches shall be carefully excavated so the bottom is within 2" from the highest to the lowest points of elevation within the trench. If the bottom elevation needs adjusting after it has been trenched, it will be done by removing high points rather than filling low points. It is extremely important to insure that trenches are not over excavated during initial trenching. All fine grading within the trench will be hand done with a shovel. No loose material will be left in the trench
- All pipe openings in the tanks shall be properly grouted. This also applies to the joints around the riser.
- All tanks shall be properly back filled and compacted to prevent slump at a later date.
- Earth dams, constructed of relatively impervious material, shall be installed at the beginning and end of each lateral.
- Elevations at pinflag locations should be checked by the installer prior to beginning trenches.
- Septic tank and pump tank risers shall be a minimum of 6" above finished grade.
- System and repair is specified as an innovative installation
- Trench bottom to be 24" on system and repair
  Based on no basement



**SUITABLE FOR PRELIMINARY PLANNING PURPOSES ONLY. ALL LOTS WILL REQUIRE APPROVAL BY THE COUNTY HEALTH DEPARTMENT ON A LOT BY LOT BASIS. THIS MAP SHOULD BY USED AS A GENERAL GUIDE. SOME ADJUSTMENTS WILL BE NECESSARY IN THE FIELD DUE TO SOIL VARIABILITY AND TOPOGRAPHIC IRREGULARITIES. THIS MAP ONLY REFLECTS EXISTING SOIL SUITABILITY FOR ON-SITE SEPTIC TANK SYSTEMS. SOME OTHER CONSIDERATIONS THAT AFFECT SITE SUITABILITY THAT SHOULD BE CONSIDERED IN DEVELOPMENT DESIGN ARE:

1) 10' SETBACK FROM PROPERTY LINE
2) 100' SETBACK FROM ANY WELL
3) 50' SETBACK FROM STREAMS, PONDS OR LAKES.

See accompanying S&EC report.

GRAPHIC SCALE
1" = 50'

50 0 50 100

NOT A SURVEY

PROJECT NO. #S-1862
PROJECT MGR. BF
DRAWN BY BF
FIELD WORK BF
SCALE 1" =50
FILE Y:\Jobs\1862

Soil & Environmental Consultants, PA
230 Lafferty Court, Suite D • Concord, North Carolina 28025 • Phone (704)720-2405 • Fax (704) 720-9409

S&EC

Wheatfield
Cumberland Station
- Wheatfield Lot 18 -
REVISED COUNTY, NORTH CAROLINA
Jan 2008

SHEET TITLE: PRELIMINARY SITE PLAN SKETCH MAP

SHEET 1 OF 1

PRESSURE MANIFOLD SYSTEM
FOR WASTEWATER TREATMENT

Owner: Corinthian Builders

Address:

Phone:
County: Iredell
Location: Wheatfield Lot 18
Source of Wastewater Flow: 3 bedroom home
Estimated Daily Wastewater Production: 360 gpd
System Flow: 35.78

Design Specifications

Drainfield Size: 345
Soil Loading Rate: 0.275
Depth of Gravel in Trench: NA
Gravel Size: N/A
Trench Depth: 24
Trench Width: 36 in.
Septic Tank Size: 1000
Pump Tank Size: 1000
Estimated Supply Line Length: 140
Supply Line Diameter: 2 in. SCH 40 PVC
Supply Line Volume: 24.36
Dosing Volume: ~~225.28~~ ~~145.76~~ .75 168 − .66 148
Supply Manifold: 4 in. SCH 80 PVC
Supply Manifold Length: 3.5 Ft.
Supply Manifold Volume: 2.08

Recommended Float Controls: SJE Sensor Float Control Switches as Required for Control Panel or County Approved Equivalents
Recommended Control Panel: SJE-Rhombus Model 112 (NEMA 4x) Control Panel or County Approved Control Panel.
Pressure Head: 2 ft.
Friction Head: 3.46
Estimated elevation Head: 6.30
Total Dynamic Head: 13.52
Threaded Union: In Tank
Gate Valves: 1 in Tank
1 at Pressure Manifold
Check Valves: In Tank
Anti-Siphon Hole: no
Recommended Pump: Myers Model ME50 or County Approved Effluent Rated Pump Capable of Delivering ~13.52 ft.of Head at ~35.78 gpm Total Flow

Wheatfield
PRESSURE MANIFOLD DESIGN

DESIGN FLOW:	360
SOIL APPLICATION RATE:	0.275 gpd/ft.^{2}
TOTAL AREA TRENCH BOTTOM:	1035
TOTAL LATERAL LENGTH:	345
NUMBER OF FIELDS:	1
LATERAL LENGTH REQUIRED PER FIELD:	327
SUPPLY LINE LENGTH:	140
TOTAL DYNAMIC HEAD:	13.52
MANIFOLD SIZE:	*4* in.SCH 80 PVC
DOSING VOLUME:	~~225.28~~ 168 Ga.
PUMP TANK DRAW DOWN*:	~~10.7~~ 8. Inches
SEPTIC TANK SIZE:	1000
PUMP TANK SIZE:	1000
RECOMMENDED PUMP:	Myers Model ME50 or County Approved Effluent Rated Pump Capable of Delivering ~13.52 ft.of Head at ~35.78 gpm Total Flow

**Pump tank draw down based on a volume basis of 21 gallons per inch. Draw down may vary among pump tank manufacturers.*

Wheatfield Lot 18

Project No. 5-1862

LAYOUT FOR 3 BEDROOM HOME

August-08

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	Designed LINE LENGTH
TBM		3.0			100.00	
INSTR. 1			103.00			
			System			
4b	Red			4.0	99.00	50
5	Pink			4.4	98.60	100
6	Blue			4.9	98.10	100
7	Red			5.3	97.70	95
					Total	**345**
			Repair			
1	Blue			2.8	100.20	40
2	Yellow			3.2	99.80	100
3	Orange			3.7	99.30	130
4a	Red			4.0	99.00	57
					Total	**327**

	LINE LENGTH	Design LTAR	SYSTEM TYPE	Innovative Type	DISTRIBUTION	Trench Depth	Soil LTAR
SYSTEM	345	0.254	Innovative	25%	Pressure Manifold	24	0.275
REPAIR	327	0.275	Innovative	25%	Pressure Manifold	24	0.275

Notes:

**TBM top of back left property stake

**Nitrification lines are demonstrated on contour via colored pin flags

**BS, HI, and FS indicate rod readings

**Flagged line length may be longer than design length


Wheatfield Lot 18

SYSTEM

Line #	Color	Elevation	Length	Hole Size	Flow/Tap	gpd	Trench Area	Flow/foot
4b	Red	99	50	SCH 80 1/2	5.48 ~~25.78~~	55.14	150	0.11
5	Pink	98.6	100	SCH 80 3/4	10.1 4.7	101.62	300	0.10
6	Blue	98.1	100	SCH 80 3/4	10.1 4.7	101.62	300	0.10
7	Red	97.7	95	SCH 80 3/4	10.1 4.7	101.62	285	0.11
	total	feet =	345	gal/min =	35.78			
			Des. Flow	360				
			Pump Run=	~~18.06~~ 4.7				
			soil LTAR	0.275				

Wheatfield Lot 18
REPAIR

Line #	Color	Elev	Length	Hole Size	Flow/Tap	gpd	Trench Area	Flow/Foot
1	Blue	100.2	40	SCH 80 1/2	5.48	47.09	120	0.14
2	Yellow	99.8	100	SCH 40 3/4	12.5	107.42	300	0.13
3	Orange	99.3	130	SCH 80 1 IN.	16.8	144.38	390	0.13
4a	Red	99.0	57	SCH 40 1/2	7.11	61.10	171	0.12
	total	feet =	327	gal/min =	41.89			
			Des. Flow	360				
			Pump Run=	8.59				
			LTAR	0.275				




NOTES

1. TANK DIMENSIONS VARY BY MANUFACTURER.

1000 GALLON SEPTIC TANK

PROJECT NO. 4591	PROJECT NAME: **Wheatfield Lot 18**	S&EC Soil & Environmental Consultants, Inc.
PROJECT MGR.		11010 Raven Ridge Road Raleigh, North Carolina 27614 Phone: (919) 846-5900 Fax: (919) 846-9467
SCALE NTS	SHEET TITLE: SEPTIC TANK DIAGRAM	Web Page: www.SandEC.com

8



NOTES


1. TANK DIMENSIONS VARY BY MANUFACTURER.
2. DRAWDOWN WILL VARY WITH TANK DIMENSIONS. DRAWDOWN SHOWN BASED ON 21 GALLONS PER INCH.

1000 GALLON PUMP TANK

PROJECT NO. 5-1862 PROJECT MGR.	PROJECT NAME: Wheatfield Lot 18	S&EC Soil & Environmental Consultants, Inc. 11910 Raven Ridge Road Raleigh, North Carolina 27614 Phone: (919) 846-5900 Fax: (919) 846-9467 Web Page: www.SandEC.com
SCALE NTS	SHEET TITLE: PUMP TANK DIAGRAM	

TAP SIZES


LINE No.	TAP SIZE
4b	1/2" SCH. 80
5	3/4" SCH. 80
6	3/4' SCH. 80
7	3/4" SCH. 80



MODEL 112 Control Panel


Single phase, simplex motor contactor control.

The Model 112 control panel provides a reliable means of controlling one 120, 208, or 240 VAC single-phase pump in pump chambers, sump pump basins, irrigation systems and lift stations. Two control switches activate a magnetic motor contactor to turn the pump on and off. If an alarm condition occurs, an additional alarm switch activates the audio/visual alarm system.



Indoor *Indoor/outdoor*

Model Shown
1121W914X



1. **Enclosure** measures 8 x 8 x 4 inches (20.32 X 20.32 X 10.16 cm). Choice of NEMA 1 (steel for indoor use), or NEMA 4X (ultraviolet stabilized thermoplastic with removable flanges for outdoor or indoor use).

   * Options selected may increase enclosure size and change component layout.

2. **Magnetic Motor Contactor** controls pump by switching hot electrical lines.
3. **HOA Switch** for manual pump control (mounted on circuit board).
4. **Green Pump Run Indicator Light** (mounted on circuit board).
5. **Float Switch Terminal Block** (mounted on circuit board).
6. **Alarm and Control Fuses** (mounted on circuit board).
7. **Alarm and Control Power Indicators** (mounted on circuit board).
8. **Pump Input Power and Pump Connection Terminal Block**
9. **Ground Lug**
10. **Terminal Block Installation Label**
11. **Circuit Breaker** (optional) provides pump disconnect and branch circuit protection.

STANDARD ALARM PACKAGE (other options available)

12. **Red Alarm Beacon** provides 360° visual check of alarm condition. **Note:** NEMA 1 style utilizes a door mounted indicator in lieu of a beacon.
13. **Alarm Horn** provides audio warning of alarm condition (83 to 85 decibel rating). **Note:** NEMA 1 style utilizes an internally mounted buzzer (83 to 85 decibel) in lieu of horn.
14. **Exterior Horn Test/Normal/Silence Switch** allows alarm horn to be silenced and testing of horn and light to ensure proper operation of alarm system.
15. **Horn Silence Relay** automatically resets alarm after alarm condition has been resolved (mounted on circuit board).

FEATURES

- Entire control system (panel and switches) is UL Listed to meet and/or exceed industry safety standards
- Dual safety certification for the United States and Canada
- Standard package includes three 20' Sensor Float® control switches
- Complete with step-by-step installation instructions
- Three-year limited warranty

c UL us
LISTED

SJE-Rhombus CONTROLS
SJ ELECTRO SYSTEMS, INC.
PO Box 1708, Detroit Lakes, MN 56502
1-888-DIAL-SJE 1-218-847-1317
1-218-847-4617 Fax
email: sje@sjerhombus.com
www.sjerhombus.com

112							

MODEL 112

ALARM PACKAGE
- 0 = select options or no alarm package
- 1 = alarm package (includes test/normal/silence switch, fuse, red light, horn & float)

ENCLOSURE RATING
- I = Indoor, NEMA 1 (metal)
- W = Weatherproof, NEMA 4X (engineered thermoplastic)

STARTING DEVICE
- 1 = magnetic motor contactor 120/208/240V
- 9 = magnetic motor contactor 120V only

PUMP FULL LOAD AMPS
- 0 = 0-7 FLA
- 1 = 8-15 FLA
- 2 = 16-20 FLA
- 3 = 21-30 FLA

PUMP DISCONNECTS
- 0 = no pump disconnect
- 1 = pull-out with safety deadfront in a 10"x8" enclosure
- 4 = circuit breaker

FLOAT SWITCH APPLICATION
- H or L = pump down or pump up
- X = no floats

OPTIONS *Listed below*

★ Options selected may increase enclosure size and change component layout.

If additional features are required, call the factory for a quote on either a Pro-Line or Engineered Custom control panel system.

CODE	DESCRIPTION
1A	Red beacon only / no audio *must select 1E if floats included*
1C	Horn only / no visual *must select 1E if floats included*
1E	Alarm float
3A	Alarm flasher
★ 4A	Low level cutout *select option 4D if floats included*
★ 4B	Red low-level indicator & alarm *must select 4A also*
4D	Low-level float
6A	Auxiliary alarm contact, form C type
★ 8A	Elapsed time meter
★ 8C	Event (cycle) counter
10E	Lockable latch - NEMA 4X
10E	Lockable latch - NEMA 1
★10F	Lightning arrester
★10K	Anti-condensation heater

CODE	DESCRIPTION
11C	NEMA 1 alarm panel *must select option 6A*
11D	NEMA 4X alarm panel *must select option 6A*
15A	Control / alarm circuit breaker *Does not include the circuit board as in standard.*
16A	10' cord in lieu of 20'
16B	15' cord in lieu of 20'
16C	30' cord in lieu of 20'
16D	40' cord in lieu of 20'
17A	SJE SignalMaster® / mounting strap ●
17B	SJE SignalMaster® / externally weighted ●
17C	Sensor Float® / internally weighted ▲
17D	Sensor Float® / externally weighted ▲
17E	Sensor Float® Mini / pipe clamp ▲
17F	Sensor Float® Mini / externally weighted ▲
19X	Door mounted pump run indicator
21A	Pumpmaster® in lieu of on/off switches ●
21B	PumpMaster® Plus in lieu of on/off switches ●
21C	Super Single® in lieu of on/off switches ▲
21D	Double Float™ in lieu of on/off switches ▲

● Mechanically-activated ▲ Mercury-activated

SAMPLE

MODEL 112 | 1 | W | 9 | 1 | 4 | H | 3A 8A

- **Alarm Package** — 1
- **Enclosure Rating** — W
- **Starting Device** — 9
- **Pump Full Load Amps** — 1
- **Pump Disconnect** — 4
- **Float Switch Application** — H
- **Options: Alarm Flasher, Elapsed Time Meter** — 3A 8A

© SJE-Rhombus Printed in USA 01/00

SENSOR FLOAT® control switch

Mercury-activated, narrow-angle float switch designed to activate pump control panels and alarms.



This narrow-angle sensing device is used to accurately monitor liquid levels in sewage and non-potable water applications. The Sensor Float® control switch is not sensitive to rotation and is suitable for use with intrinsically safe circuits. Contact SJE-Rhombus regarding specific intrinsically safe applications.

Normally Open Model (high level)
The control switch turns on (closes) when the float tips slightly **above** horizontal signaling a high level, and turns off (opens) when the float drops slightly below horizontal.

Normally Closed Model (low level)
The control switch turns on (closes) when the float drops slightly **below** horizontal signaling a low level, and turns off (opens) when the float tips slightly above horizontal.

FEATURES

- Suitable for use with intrinsically safe circuits.
- Not sensitive to rotation.
- Control differential of .5 inches (1 cm) above or below horizontal.
- UL Listed for use in non-potable water and sewage.
- CSA Certified.
- Three-year limited warranty.

LR54245 LISTED 83N2

Hydraulic

OPTIONS

This switch is available:

- for normally open (high level) applications or normally closed (low level) applications.
- in standard cable lengths of 10, 15, 20, or 30 feet and 3, 5, 6, or 10 meters.
- with three mounting options that allow for flexibility in installation:

  Mounting Clamp: for applications where the switch can be attached to a discharge pipe or similar mounting device.

  Internally Weighted: for applications where the switch can be suspended from above.

  Externally Weighted: for applications where the switch can be suspended from above.

SPECIFICATIONS

CABLE: flexible 18 gauge, 2 conductor (UL,CSA) SJOW, water-resistant (CPE) jacket

FLOAT: 3.38 inch diameter x 4.55 inch long (8.58 cm x 11.56 cm), high-impact, corrosion resistant, PVC housing for use in sewage and non-potable water up to 140°F (60°C)

MAXIMUM WATER DEPTH: 30 feet (9 meters), 13 psi

MERCURY TILT SWITCH: single pole, single throw, mercury-to-mercury contacts, hermetically sealed in a steel capsule and epoxy sealed in the float housing

ELECTRICAL: 5 amp, 120/230 VAC, 50/60 Hz

CONTROLS SJE-Rhombus SJ ELECTRO SYSTEMS, INC.
PO Box 1708, Detroit Lakes, MN 56502
1-888-DIAL-SJE | 1-218-847-1317
1-218-847-4617 Fax
email: sje@sjerhombus.com
www.sjerhombus.com

Sensor Float® control switch installation instructions

⚠WARNING ELECTRICAL SHOCK HAZARD
Disconnect power before installing or servicing this product. A qualified service person must install and service this product according to applicable electrical and plumbing codes.

⚠WARNING EXPLOSION OR FIRE HAZARD
Do not use this product with flammable liquids. Do not install in hazardous locations as defined by National Electrical Code, ANSI/NFPA 70.

Failure to follow these precautions could result in serious injury or death. Replace product immediately if switch cable becomes damaged or severed. Keep these instructions with warranty after installation. This product must be installed in accordance with National Electric Code, ANSI/NFPA 70 so as to prevent moisture from entering or accumulating within boxes, conduit bodies, fittings, float housing, or cable.

MOUNTING THE SWITCH

1. Place the cord into the clamp as shown in Figure B.
2. Locate clamp at desired activation level and secure the clamp to the discharge pipe as shown in Figures A and B. **Note:** Do not install cord under hose clamp.
3. Tighten the hose clamp using a screwdriver. Over tightening may result in damage to the plastic clamp. Make sure the float cable is not allowed to touch the excess hose clamp band during operation.
4. Bring cable leads back to control device and wire according to Figure C.
5. Check installation. Allow system to cycle to insure proper operation.

Note: All hose clamp components are made of 18-8 stainless steel material. See your SJE-Rhombus supplier for replacements.

Figure A





Figure B



INTERNAL WEIGHT

1. Determine desired activation level.
2. Suspend switch 7 inches (18 cm) below desired activation level as shown in Figure D. Switch remains partially submerged during the "on" tipping action. Switch can be totally submerged and still continue to operate properly.
3. Wire cable leads directly into control device as shown in Figure C.
4. Check installation. Allow system to cycle to insure proper operation.

Figure C - Wiring Diagram





Figure D




CABLE WEIGHT

1. Determine desired activation level.
2. Suspend switch and cable weight at desired activation level as shown in Figure E.
3. Wire cable leads directly into control device as shown in Figure C.
4. Check installation. Allow system to cycle to insure proper operation.

Cable weight is attached to switch cable at the factory. To adjust:

1. Release clip.
2. Adjust cable weight to desired position.
3. Lay switch cable in weight channel.
4. Align clip with weight channel and slide towards switch cable as shown in Figure E.
5. Snap clip snugly up to cable, moving clip to tightest possible position.

Figure E




CONTROLS
SJE-Rhombus®
SJ ELECTRO SYSTEMS, INC.
22650 County Highway 6 ■ P.O. Box 1708 ■ Detroit Lakes, Minnesota 56502 USA
1-888-DIAL-SJE (1-888-342-5753) ■ Phone: 218-847-1317 ■ Fax: 218-847-4617
E-mail: sje@sjerhombus.com

Instl. Instr. PN 1009648A
Cat. Page PN 1009509A


©SJE-Rhombus
Printed in USA 03/00

ME SERIES

1/2 through 1-1/2 HP
Effluent Pumps



Double Seal



Single Seal

THE MYERS ME SERIES EFFLUENT PUMPS ARE DESIGNED SPECIFICALLY FOR TODAY'S EFFLUENT PRESSURE DISTRIBUTION MOUNDS, TRENCHES AND HIGH FLOW DRAINAGE APPLICATIONS. The ME Series effluent pumps with their efficient two vane, enclosed impellers, provide the ideal performance for optimum dosing. ME Series pumps are constructed of only corrosion resistant materials like cast iron, stainless steel and thermoplastics to assure that they will perform for years to come in the harsh effluent environment and drainage applications. For more information, call your Myers distributor today or the Myers Ashland, Ohio sales office at 419/289-1144.

ADVANTAGES BY DESIGN

IDEAL FOR USE IN MOUND AND TRENCH PRESSURE DISTRIBUTION SYSTEMS

- High efficiency, two vane, enclosed impeller provides ideal performance for most efficient dosing.
- Impeller passes full ¾ inch solids.
- Enclosed impeller design eliminates possibility of jamming or corrosion between impeller and volute.

DURABLE MOTOR WILL DELIVER MANY YEARS OF RELIABLE SERVICE

- Oil-filled motor for maximum heat dissipation and constant bearing lubrication.
- High torque, permanent split capacitor (PSC), single phase motors. No starting switches or relays to wear out.
- Optional seal leak probe warns of seal leak condition. (Dual seal motors only.) Helps prevent costly motor damage.
- Motors have on winding current and temperature sensitive overload. (Single phase only.)

THE ME SERIES EFFLUENT PUMPS ARE DESIGNED FOR YEARS OF MAINTENANCE FREE OPERATION

- Volute seal ring is replaceable. Restores pump to original performance if wear should occur.
- Motor is held in place by 4 screws. Easily removed if service is ever needed.

PRODUCT CAPAILITIES

Capacities To	120 GPM	454 LPM
Heads To	95 ft.	28.9 m
Max. Spherical Solids	¾ in.	19 mm
Liquids Handling	domestic effluent & drain water	
Intermittent Liquid Temp.	up to 140° F	up to 60° C
Motor Electrical Data	1/2 HP 115 volts, 1 ph 1/2 to 1-1/2 HP 230 volts, 1 ph 208, 230, 460, 575 volts, 3 ph oil-filled, permanent split capacitor type, 1 ph, 3450 rpm, 60 Hz	
Motor Insulation	Class B (130° C)	
Third Party Approvals	UL, CSA	
Acceptable pH Range	6-9	
Specific Gravity	9-1.1	
Viscosity	28-35 SSU	
Discharge, NPT	2 in.	50.8 mm
Min. Sump Dia. Simplex Duplex	24 in. 36 in.	61 cm 91.4 cm

Construction Materials	
Motor Housing, Volute	cast iron, Class 30, ASTM A48-76
Enclosed Two Vane Impeller Standard Optional	engineered thermoplastic bronze
Impeller Wear Ring	304 SST
Volute Sealing Ring	Buna-N
Shaft	416 SST
Power Cord 1/2 HP 1 Ph 3/4 - 1-1/2 HP 1 Ph All 3 Ph	 20 ft. 16/3 SJOW/SJOW-A 20 ft. 14/3 SJOW/SJOW-A 20 ft. 14/4 SOW/SOW-A
Shaft Seals Standard Optional Opt. Lower	single carbon & ceramic tandem carbon & ceramic tungsten carbide
Fasteners	300 Series SST

WHERE INNOVATION MEETS TRADITION

ISO 9001 Certified Company

Myers
PENTAIR PUMP GROUP

ME SERIES

1/2 through 1-1/2 HP
Effluent Pumps


POWER CORD
Jacket sealed with compression fittings. Individual wires potted with epoxy to prevent wicking in case of cord damage.

MOTOR HOUSING
Cast iron for efficient heat transfer and corrosion resistance.

BEARINGS
Upper and lower ball support rotor. Take radial and thrust loads.


MOTOR
1/2, 3/4, 1 and 1-1/2 HP single or three phase. 60 Hz, 3450 RPM. Single phase PSC motors have built-in on winding overload protection, oil-cooled and lubricated.

HIGH EFFICIENCY CAST IRON VOLUTE
Corrosion resistant. Passes ¾" spherical solids. 2" NPT discharge.



ENCLOSED TWO VANE IMPELLER
high efficiency. Passes ¾" spherical solids with stainless steel wear ring. Optional bronze construction available.


VOLUTE/IMPELLER SEAL RING
Maintains high efficiency and reduces recirculation. Replaceable.



SHAFT SEAL(S)
Carbon and ceramic faces. Optional dual tandem seals. Extends motor life.


SEAL LEAK PROBES
Optional probes (dual seal only) detect water leakage in seal housing. Activates warning light.

DIMENSIONS



Model Series	Inches (millimeters)			
	A	B	C	Γ
ME50S	16.8 (427)	4.09 (104)	1.03 (26)	12.13 (308)
ME50D	18.6 (472)	4.09 (104)	1.03 (26)	12.13 (308)
ME75S, ME100S, ME150S	16.8 (427)	4.0 (102)	1.06 (27)	12.5 (318)
ME75D, ME100D, ME150D	18.6 (472)	4.0 (102)	1.06 (27)	12.5 (318)

PERFORMANCE CURVE




K3320 9/98
Printed in U.S.A.

PRINTED WITH SOY INK

Myers
PENTAIR PUMP GROUP

F. E. Myers, 1101 Myers Parkway, Ashland, Ohio 44805-1969
419/289-1144, FAX: 419/289-6658, www.femyers.com
Myers (Canada), 269 Trillium Drive, Kitchener, Ontario N2G 4W5
519/748-5470, FAX: 519/748-2553

ELECTRIC BOX



NOTES: ELECTRICAL SYSTEM COMPONENTS SHALL BE INSTALLED TO MEET OR EXCEED MINIMUM REQUIREMENTS SPECIFIED IN THE ELECTRICAL COME. ALL WIRING SHALL BE #12 MINIMUM, AND RATED FOR DIRECT BURY. PROVIDE GROUNDING AS REQUIRED, AND PROVIDE 30" MINIMUM BURY ON CABLES. PROVIDE ONE 20 AMP, DOUBLE POLE, 230 VOLT CIRCUIT BREAKER (FOR PUMP), AND ONE 20 AMP, SINGLE POLE, 115 VOLT CIRCUIT BREAKER (FOR ALARM) IN MAIN PANEL.

CALCULATIONS


Location Wheatfield

Project Number 5-1862

Lot No: 18

No. of Bedrooms	3	
Design Flow	360	$^{gal}/_{day}$
LTAR	0.275	$^{gal}/_{ft^2\ day}$
EZ-Lay? (YES OR NO)	yes	
Supply Line Length	140	ft.
Supply Line Volume	24.36	gal.
Required Feet of Line	327	ft.
Amount of Line from Layout	345	ft.
Gallons per Minute	35.78	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	225.28	gal.
Dosing Volume	~~225.28~~ 168 (75%)	gal.

Note: Dosing Volume based on the lateral line volume.



Tank Draw Down	~~10.7~~ 8.0	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	~~6.29~~ 4.70	minutes
Estimated Elevation Head	6.3	ft.
Pressure Head	2	ft.
Friction Factor	2.47	ft./100 ft.
Friction Head	3.458	ft.
Total Dynamic Head (+15%)	13.52	ft.

(5) Ashes, garbage, and trash shall be kept out of the pit.

History Note: *Authority G.S. 130A-335(e) and (f);*
Eff. July 1, 1982;
Amended Eff. January 1, 1990.

15A NCAC 18A .1961 MAINTENANCE OF SEWAGE SYSTEMS

(a) Any person owning or controlling the property upon which a ground absorption sewage treatment and disposal system is installed shall be responsible for the following items regarding the maintenance of the system:

(1) Ground absorption sewage treatment and disposal systems shall be operated and maintained to prevent the following conditions:

(A) a discharge of sewage or effluent to the surface of the ground, the surface waters, or directly into groundwater at any time; or

(B) a back-up of sewage or effluent into the facility, building drains, collection system, or freeboard volume of the tanks; or

(C) a free liquid surface within three inches of finished grade over the nitrification trench for two or more observations made not less than 24 hours apart. Observations shall be made greater than 24 hours after a rainfall event.

The system shall be considered to be malfunctioning when it fails to meet one or more of these requirements, either continuously or intermittently, or if it is necessary to remove the contents of the tank(s) at a frequency greater than once per month in order to satisfy the conditions of Parts (A), (B), or (C) of this Paragraph. Legal remedies may be pursued after an authorized agent has observed and documented one or more of the malfunctioning conditions and has issued a notice of violation.

(2) Ground absorption sewage treatment and disposal systems shall be checked, and the contents of the septic tank removed, periodically from all compartments, to ensure proper operation of the system. The contents shall be pumped whenever the solids level is found to be more than 1/3 of the liquid depth in any compartment.

(b) System management in accordance with Tables V(a) and V(b) of this Rule shall be required for all systems installed or repaired after July 1, 1992. After July 1, 1992, system management in accordance with Tables V(a) and V(b) shall be required for all existing Type V and Type VI systems.

(c) No Improvement Permit or Construction Authorization shall be issued for Type IV, Type V, or Type VI systems, unless a management entity of the type specified in Table V(b) is specifically authorized, funded, and operational to carry out this management program in the service area where the proposed system is to be located.

(d) A local health department may be the public management entity only for systems classified Type IV, V(a) and V(b) and only when specifically authorized by resolution of the local board of health.

(e) A contract shall be executed between the system owner and a management entity prior to the issuance of an Operation Permit for a system required to be maintained by a public or private management entity, unless the system owner and certified operator are the same. The contract shall include the specific requirements for maintenance and operation, responsibilities of the owner and system operator, provisions that the contract shall be in effect for as long as the system is in use, and other requirements for the continued proper performance of the system. It shall also be a condition of the Operation Permit that subsequent owners of the system execute such a contract.

(f) Inspections of the system shall be performed by a management entity at the frequency specified in Table V(b). The management entity shall report the results of their inspections to the local health department at the specified reporting frequency. However, where inspections indicate the need for system repairs, the management entity shall notify the local health department within 48 hours in order to obtain a Construction Authorization for the repairs.

(g) The management entity shall be responsible for assuring routine maintenance procedures and monitoring requirements in accordance with the conditions of the Operation Permit and the contract.

(h) Sewage systems with multiple components shall be classified by their highest or most complex system type in accordance with Table V to determine local health department and management entity responsibilities.

(i) Sewage systems not identified in this Rule shall be classified by the Division of Environmental Health after consultation with the appropriate commission governing operators of pollution control facilities.

(j) The local health department shall routinely review the performance and operation reports submitted in accordance with Table V(b) of this Rule and shall perform an on-site inspection of the systems as required in Table V(a).

(k) The certified operator shall hold a valid and current certificate from the appropriate commission, and nothing in this Section shall preclude any requirements for system operators, in accordance with Article 3 of G.S. 90A.

TABLE V(a)

LOCAL HEALTH DEPARTMENT RESPONSIBILITIES

System Classification	System Description	Permits Required	Minimum System Review Frequency
Type I	a. Privy b. Chemical toilet c. Incinerating toilet d. Other toilet system e. Grease trap	Improvement Permit, Construction Authorization, and Operation Permit	N/A
Type II	a. Conventional septic system (single-family or 480 GPD or less) b. Conventional septic system with 750 linear feet of nitrification line or less c. Conventional system with shallow placement	Improvement Permit, Construction Authorization, and Operation Permit	N/A
Type III	a. Conventional septic system > 480 GPD (excluding single-family residence) b. Septic system with single effluent pump or siphon c. Gravity fill system d. Dual gravity field system e. PPBPS system, gravity dosed f. Large diameter pipe system g. Other non-conventional trench systems	Improvement Permit, Construction Authorization, and Operation Permit	5 yrs. (IIIb only)
Type IV	a. Any system with LPP distribution b. System with more than 1 pump or siphon	Improvement Permit, Construction Authorization, and Operation Permit	3 yrs.
Type V	a. Sand filter pretreatment system b. Any > 3,000-GPD septic tank system with a nitrification field designed for > 1500 GPD c. Aerobic Treatment Unit (ATU) d. Other mechanical, biological, or chemical pretreatment plant (< 3000 GPD)	Improvement Permit, Construction Authorization, and Operation Permit	12 mos.

Type VI	a. Any > 3,000 GPD system with mechanical, biological, or chemical pretreatment system plant b. Wastewater reuse/recycle	Improvement Permit, Construction Authorization, and Operation Permit	6 mos.

TABLE V(b)

MANAGEMENT ENTITY RESPONSIBILITIES

System Classification	Management Entity	Minimum System Inspection/Maintenance Frequency	Reporting Frequency
Type I	Owner	N/A	N/A
Type II	Owner	N/A	N/A
Type III	Owner	N/A	N/A
Type IV	Public Management Entity with a Certified Operator or a private Certified Operator	2/yr.	12 mos.
Type V	Public Management Entity With a Certified Operator or a private Certified Operator	a. 2/yr (0-1500 GPD) 4/yr (1500-3000 GPD) 12/yr (3000-10000 GPD) 1/wk (> 10000 GPD) b. 12/yr (3000-10000 GPD) 1/wk (> 10000 GPD) c. 4/yr. d. 12/yr.	6 mos.
Type VI	Public Management Entity With a Certified Operator	a. 1/wk(3000-10000 GPD) 2/wk(10000-25000 GPD) 3/wk(25000-50000 GPD) 5/wk(> 75000 GPD) b. 12/yr.	3 mos.

(l) A sewage collection, treatment, and disposal system that creates or has created a public health hazard or nuisance by surfacing of effluent or discharge directly into groundwater or surface waters, or that is partially or totally destroyed shall be repaired within 30 days of notification by the state or local health department unless the notification otherwise specifies a repair period in writing. If a system described in the preceding sentence has for any reason been disconnected, the system shall be repaired prior to reuse. The state or local health department shall use its best professional judgement in requiring repairs that will reasonably enable the system to function properly. If, for any reason, a sewage collection, treatment, and disposal system is found to be nonrepairable, or is no longer required, the system shall not be used, and may be required to have any contents removed, collapse any components and backfill, or otherwise secured as directed by the authorized agent to protect the public health and safety.

(m) When necessary to protect the public health, the state or local health department may require the owner or controller of a malfunctioning system to pump and haul sewage to an approved wastewater system during the time needed to repair the system.