Pd $195



MICHAEL ATHANAS & ASSOCIATES
LICENSED SOIL SCIENTIST
1999 CANDLEWICK DRIVE
FORT MILL, S.C. 29715
803-802-4403 (office)
803-802-4402 (fax)

Reference: Data Sheet for Lot 15/16 Combination, Wheatfield S.D., Iredell County NC
House Footprint: Refer to Drawing
Water Source: Private Well
Number of Bedrooms: 4/480gpd
Pre-determined LTAR: Initial 0.3 gpd/ft2, Repair 0.225 gpd/ft2
Suggested System Type: Initial 25% Red., Repair PPBPS
Distribution: Gravity
Proposed Trench Depth: 36"
Septic/ Pump tank size: 1000gal

Line	Actual Length	Design Length	Elevation
Pink 1	**176'**	**133'**	
Blue 2	**170'**	**133'**	
White 3	**175'**	**133'**	**N/A**
Pink 4	155'		
Blue 5	156'		
White 6	68'		

Initial System: 400' of 25% Red.
Septic Tank: 1000gal

Repair System: 379'+ PPBPS, (355 Needed)
Benchmark: N/A

Comments: Lots 15 and 16 are being combined. We are proposing a 4 bedroom, 25% reduction system with a Panel block repair. Proposed trench bottom is 36".