ICHD - ENVIRONMENTAL HEALTH DIVISION

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625 PERMIT # AP 325618

SEPTIC: IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4762 -- 02 -- 7848

APPLICANT/OWNER: Ridgewater Construction LLC APPLICANT ADDRESS: PO Box 4211 Mooresville NC 28117

SITE ADDRESS: 116 Witherspoon Ln Statesville NC PHONE: 704-657-4876 ALT. PHONE —

SITE DIRECTIONS: 77N to exit 45 Take R onto Shiloh to Clements SAP CONTROLLED: ☐ YES ☒ NO

SUBDIVISION: Loyd Acres SECTION: — LOT # 12 LOT AREA: .46 AC DESIGN FLOW: 360 L.T.A.R.: .30

Septic Tank	1000	(gal)	STB	760	Date	5/1/22	☒ New System	☐ Repair	☐ Expansion	System Type: I II (III) IV V VI	
Pump Tank	—	(gal)	PT	—	Date	—	System Description:	Pump to Serial Distribution -25%			
Pump Make	—	Model		—	Serial #	—	Repair System Description:	PDBDS -50% Reduction			
# Nitrification Fields	1	# Lines		4	Linear Ft	300	Maintenance Agreement Required:	☐ YES	☒ NO		
Trench Width	36.	Trench Bottom Depth(Low side)		34in Low	Gravel Depth	—		☐ GRAVITY	☒ PRESSURE		

☒ Residence	No. Bedrooms	3	**Water Supply**
☐ Business	No. Persons	6	☒ Private
☐ Other	No. Employees		☐ Public
☒ Slab	☐ Crawl Space		☐ Community
☐ Basement w/plumbing		☐ Basement w/o plumbing	

Comments / Conditions:


INITIAL SITE SKETCH

This permit is issued pursuant to Section 11.(c) of S.L. 2018-114 using the signed and Sealed LSS Evaluation by:

LEY Soil & Onsite Wastewater Consulting PLLC

LSS# 1080 Dated Feb 7, 2022

AS BUILT SKETCH



FOR SEPTIC FINAL INSPECTION CALL: 704-664-3703 between 8am-9am the day the inspection is needed. Be sure to speak with an inspector to confirm your time.

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. **CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION**

☐ **IMPROVEMENT PERMIT** *with plat valid without expiration.* ☒ **IMPROVEMENT PERMIT** *with site plan valid for 60 mos.* ☒ **AUTHORIZATION TO CONSTRUCT** *valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.*

Owner / Applicant Signature: Rachael McCall Date: 5-4-2022 Installed by: Rowen Septic

IMPROVEMENT PERMIT by: Benjamin A Botts Date: 5-2-2022 OPERATION PERMIT by: Matt Walker Date: 6/21/22

AUTHORIZATION TO CONSTRUCT by: Benjamin A Botts Date: 5-2-2022 Existing System Inspected by: Date:

FOR SEPTIC FINAL INSPECTION: CALL 704-664-3703 between 8am-9am the day the inspection is needed.


LTE

Scanned from a M...

PRELIMINARY PLAN
NOT FOR RECORDATION
CONVEYANCES
AND/OR SALES

Septic System Repair
Area Exempt Due To
Property Being Deeded
And Recorded In 1973

Well Site: Stay A minimum of (50ft.)
Away From All Septic & Repair Areas
And (25ft.) Away From All Structures



TAX ID: 4782-03-7028
LOT 2
BONNIE SUE T MOOSE LIV TR &
HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1403
PB: 11 PG: 39

TAX ID: 4782-03-8028
LOT 1
BONNIE SUE T MOOSE LIV TR &
HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

*Neighbors Septic System (Lot #1)

Set #4 Rebar

S71°20'43"E 100.00'

LOT 12
0.46 Acres

Proposed Well Site

Proposed House Box

40.0'

40.0'

40.0'

31.9'

N25°59'28"E 200.14'

S25°59'29"W 200.21'

(10Ft.) PPBPS Repair . 3

(10Ft.) PPBPS Repair . 3

Blue

Pink

Red

Yellow

(5')

(5')

N71°18'37"W 99.99'

Witherspoon Ln
60' Public R/W
PB: 11 Pg

1950
JV TR &
LV TR
DS

U Ln
R/W
39

LEY
SOIL & Onsite Wastewater CONSULTING PLLC

(336)-608-9206 gyoung127@icloud.com
(336)-940-7672 geaster56@icloud.com
(704)-310-6529 Jll2663@gmail.com
NC Licensed Soil Scientist, NC Environmental Health Specialist

Date: February 7, 2022

Project Name: Ridgewater Construction, PO Box 4211, Mooresville, NC

SESSION LAW 2018-114, SECTION 11.(c)/HOUSE BILL 374, SECTION 11.(c)
AUTHORIZATION FORM

LEY Soil & Onsite Wastewater Consulting has been contracted to evaluate soil, design and submit a septic system proposal to Iredell (county) on behalf of Ridgewater Construction (owner/applicant) for the property located at Loyd Acres Lot – 12 - 4762-02-7848 (address/PIN).

The Licensed Soil Scientist (LSS) Evaluation attached to this application is to be used to produce design and construction features for permitting in accordance with SL 2018-114 Section 11.(c).

The LSS Evaluation is being submitted pursuant to and meets the requirements of SL 2018-114 Section 11. (c).

LICENSED SOIL SCIENTIST GENE YOUNG 1020 STATE OF NORTH CAROLINA

Owner/Owners Legal Representative: Ridgewater Construction LLC C/O Rachael McClure, MM

Mailing Address: PO Box 4211 Mooresville, NC 28117

Telephone Number: 704.657.4876

Email Address: Rachael@ridgewatercustomhomes.com

DESIGN SPECIFICATIONS

Owner:	RidgeWater Construction
Address:	PO Box 4211 Mooresville, NC 28117
Phone:	704-657-4876
County:	Iredell
Pin Number	4762-02-7848 Lot 12
Drainfield Design Flow (gpd):	360
Loading/Soil Application Rate (gpd/ft.^{2}):	0.3
Depth of Gravel in Trench:	NA (25% reduction)
Gravel Size:	NA (25% reduction)
Total Lateral Length From Layout:	300
Total Lateral Length Required:	300
Trench Depth:	34 Low Side
Trench Width:	36 in.
Trench Spacing:	9 ft. on center
Trench Bottom Area:	1200
Repair Trench Spacing:	8
Repair Trench Depth:	32 in. Low side
Septic Tank Size:	1000
Pump Tank Size:	1000
Estimated Supply Line Length:	30
Supply Line Diameter:	2 in. SCH 40 PVC
Supply Line Volume:	5.22
Dosing Volume:	137.13
Pump Tank Draw Down:	6.5
Recommended Dosing Controls:	Float Control Switches as Required for Control Panel or County Approved Equivalents
Recommended Control Panel:	NEMA 4X Control Panel or County Approved Control Panel.
Pressure Head:	2 ft.
Friction Head:	3.48
Elevation Head:	14.00
Total Dynamic Head:	20.45
Threaded Union:	In Tank
Gate Valves:	1 in Tank 1 at Pressure Manifold
Check Valves:	In Tank
Anti-Siphon Hole:	NA

**Pump tank draw down based on an industry standard volume basis of 21 gallons per inch. Draw down may vary among pump tank manufacturers.*

Comments: **Iredell County permission to change septic tank location and distribution type and from a pump system to a gravity fed system**

FIELD LAYOUT SPECIFICATIONS

LAYOUT FOR 3 BEDROOM HOME

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM							
INSTR. 1							
HOUSE							
TANK							
1	*Blue*					*80*	*80*
2	*Pink*					*80*	*80*
3	*Red*					*80*	*80*
4	*Yellow*					*80*	*60*
5							
6							
7							
8							
9							
10							
11							
12							
13							
15							
16							
					Total	**320**	**300**

	LINE LENGTH	SYSTEM TYPE	SOIL LTAR GPD/FT[1]	TRENCH SYSTEM	DISTRIBUTION	
* *System*	*300*	*ACCEPT.*	*0.300*	*25% RED.*	Serial	
Repair		MOD.	0.300	PPBPS		50% REDUCTION

Notes:

CALCULATIONS

Location Loyd Acres

Lot No: 12

No. of Bedrooms	3
Design Flow	360 $^{gal}/_{day}$
LTAR	0.3 $^{gpd/ft^2}$
25% RED.? (YES OR NO)	YES
Supply Line Length	30 ft.
Supply Line Volume	5.22 gal.
Amount of Line Required	300
Amount of Line from Layout	300 ft.
Gallons per Minute	41.3 $^{gal}/_{min}$
Required Septic Tank Capacity	1000 gal.
Required Pump Tank Capacity	1000 gal.
Lateral Line Volume	195.9 gal.
Dosing Volume	137.13 gal.

Note: Dosing Volume based on 70% of lateral line volume

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42

Tank Draw Down	6.5 *Generic Draw Down of 21 gal.per in.*
Pump Run Time	3.32 minutes
Elevation Head	14 ft.
Pressure Head	2 ft.
Friction Factor	3.48 ft./100 ft. *(From the interpolater.)*
Friction Head	1.04 ft.
Total Dynamic Head (+20%)	20.45 ft.


Sheet ____ of ____
PROPERTY ID #: ____
COUNTY: IREDELL

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM
(Complete all fields in full)

OWNER: RIDGEWATER HOMES APPLICATION DATE 11/17/21
ADDRESS: BEVIS LN. LOT # 12 STATESVILLE, N.C. DATE EVALUATED: 12/28/21
PROPOSED FACILITY: 3BR HSE PROPOSED DESIGN FLOW (.1949): 360 PROPERTY SIZE: 100'x200
LOCATION OF SITE: BEVIS LN. PIN # 4762027848.000 PROPERTY RECORDED: ____
WATER SUPPLY: (Private) Public . (Well) Spring . Other ____
EVALUATION METHOD: (Auger Boring) . Pit . TYPE OF WASTEWATER: . (Sewage) . Industrial Process . Mixed

Landscape Position (1940)	L	L	L								
Slpoe%	<5%	<5%	<5%								
H 1 Depth (1943)	0-30	0-12	0-13								
H1 texture 1941	C	SL	SL								
H1 Structure 1941	Blky	GR	GR								
H1 Consistance 1941	FI SP	FR SP	FR SP								
H1 Mineralogy 1941	SE	SE	SE								
H 2 Depth (1943)	30-48	12-48	13-38								
H2 texture 1941	BC/C	C	C								
H2 Structure 1941	Blky	Blky	Blky								
H2 Consistance 1941	FI SP	FI SP	FI SP								
H2 Mineralogy 1941	SE	SE	SE								
H 3 Depth (1943)			38-48								
H3 texture 1941			BC/C								
H3 Structure 1941			Blky								
H3 Consistance 1941			FI SP								
H3 Mineralogy 1941			SE								
H 4 Depth (1943)											
H4 texture 1941											
H4 Structure 1941											
H4 Consistance 1941											
H4 Mineralogy 1941											
LTAR	.3	.3	.3								

Description	Initial System	Repair	Other Factors 1946
System Type	25%	50%	Site Classification PS
LTAR	.3	.3	



Evaluated by GARY EASTER LSS, JEFF LINKREHS

I, JOEL H. PATTERSON III, CERTIFY THAT THIS PLAT WAS DRAWN UNDER MY SUPERVISION FROM AN ACTUAL SURVEY MADE UNDER MY SUPERVISION; DEED DESCRIPTION AND/OR MAP BOOK SEE, PAGE NOTE #2; THAT THE BOUNDARIES NOT SURVEYED ARE CLEARLY INDICATED AS DRAWN FROM INFORMATION FOUND IN BOOK ____ PAGE ____; THAT THE RATIO OF PRECISION AS CALCULATED IS 1:10,000+; THAT THIS PLAT WAS PREPARED IN ACCORDANCE WITH THE STANDARDS OF PRACTICE FOR LAND SURVEYING IN NORTH CAROLINA (21 NCAC 56.1800). WITNESS MY ORIGINAL SIGNATURE, REGISTRATION NUMBER AND SEAL THIS ____ DAY OF _____ 2022.


PRELIMINARY

JOEL H. PATTERSON III, PLS
LICENSE NUMBER: L-3717

PRELIMINARY PLAN NOT FOR RECORDATION CONVEYANCES AND/OR SALES

NORTH CAROLINA PROFESSIONAL SEAL L-3717 LAND SURVEYOR JOEL H. PATTERSON, III

PLAT BOOK: 11
PAGE: 39
DATED: June 6, 1972



VICINITY MAP
NOT TO SCALE

TAX ID: 4762-03-7028
LOT 2
BONNIE SUE T MOOSE LIV TR & HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

TAX ID: 4762-03-8028
LOT 1
BONNIE SUE T MOOSE LIV TR & HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

TAX ID: 4762-02-6950
LOT 11
BONNIE SUE T MOOSE LIV TR & HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

Set #4 Rebar

S71°20'43"E 100.00'

LOT 12
0.46 Acres±

Well Site (Set)

Proposed House Box

24.7'
40.0'
40.0'
40.0'
40.0'
31.9'

N25°39'29"E 200.14'

S25°39'29"W 200.21'

Witherspoon Ln
60' Public R/W
PB: 11 PG: 39

Cottontail Ln
60' Public R/W
PB: 11 PG: 39

N71°18'37"W 99.99'

Found #4 Rebar

Blue
Red
Red
Yellow

95.0'

R/W
OU
no

LEGEND

R/W = Right-of-Way
—OU— = Overhead Utility
Red (Color) = Septic Lines
O = Iron Found
O = Iron Set

GRAPHIC SCALE

30 0 15 30

(IN FEET)
1 inch = 30 feet

SURVEYOR NOTES

1. ALL DIMENSIONS SHOWN ARE IN US SURVEY FEET AND DECIMALS THEREOF AND ARE HORIZONTAL GROUND DISTANCES UNLESS OTHERWISE INDICATED. AREA BY COORDINATE METHOD.
2. THIS SURVEY IS BASED ON DEED BOOK 2830 PAGE 1405 AND PLAT BOOK 11 PAGE 39 AS RECORDED AT THE IREDELL COUNTY REGISTER OF DEEDS.
3. THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE EXAMINATION BY AN ATTORNEY. THE PROPERTY MAY BE SUBJECT TO RECORDED OR UNRECORDED RIGHTS-OF-WAY, EASEMENTS, RESTRICTIVE COVENANTS OR CONDITIONS NOT OBSERVED OR SHOWN HEREON.
4. SUBJECT PARCEL LIES WITHIN A SUBDIVISION PREVIOUSLY TIED TO NC GRID.
5. BASIS OF BEARINGS: PLAT BOOK: 11, PAGE: 39 - DATED: JUNE 13, 1972.
6. ALL CORNERS "FOUND" OR "SET" ARE FLUSH WITH THE GROUND, UNLESS OTHERWISE NOTED. POINTS NOT LABELED "FOUND" OR "SET" ARE COMPUTED POINTS.
7. THE LOCATION OF UTILITIES AS SHOWN HEREON, WHETHER PUBLIC OR PRIVATE, ARE BASED ON THE LOCATION OF VISIBLE ABOVE GROUND APPURTENANCES ONLY. OTHER UTILITIES WHICH WERE NOT OBSERVED AND NOT SHOWN HEREON MAY EXIST. IT IS THE OWNER'S/TENANTS RESPONSIBILITY TO VERIFY THE LOCATION PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION. PATTERSON LAND SURVEYING, P.A. CANNOT ASSUME RESPONSIBILITY FOR MISIDENTIFICATION OR OMISSION OF UNDERGROUND UTILITIES.
8. THIS SURVEY IS OF AN EXISTING PARCEL OR PARCELS OF LAND AND DOES NOT CREATE A NEW STREET OR CHANGE AN EXISTING STREET.
9. THIS PROPERTY LIES IN FLOOD ZONE "X" AS SHOWN ON FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL 3710475200J, WITH AN EFFECTIVE DATE OF MARCH 15, 2008.

PLOT PLAN

LOT 12 – LOYD ACRES – SECT. TWO
PLAT BOOK: 11 PAGE: 39

CHAMBERSBURG TOWNSHIP, IREDELL COUNTY, NC

Prepared For:
RIDGEWATER CUSTOM HOMES
P.O. BOX 4211
MOORESVILLE NC, 28115

PATTERSON LAND SURVEYING, P.A.
NC LICENSE #: C-3390
P.O. BOX 5010, MOORESVILLE, NC 28117
PHONE: 704-663-0110 EMAIL: pattersonlandsurveying@gmail.com

Drawn By: SAG	Checked By: JHP	Scale 1" = 30'	Project No. 21080
Tax Parcel: 4762-02-7848			
Date: January 25, 2022			Sheet No. 1 of 1
File: 21080-Lot 12 Loyd Acres.dwg			

Installer Information

Be sure to read the permit very carefully before submitting bid.

The following details must be considered along with all other considerations:

- Tanks shall be approved by NC DHHS, and certification supplied by the manufacturer
- All tanks shall be properly back filled and compacted to prevent slump in the future
- The installer is responsible for final grades and returning that grade to original, with the exception of added structural features
- The supply trench shall be compacted to eliminate any cavities left during initial fill placement
- Installation of the system shall be completed during dry conditions in order to protect the soil structure
- All fittings shall be pressure rated fitting
- All joints shall be cleaned with PVC pipe cleaner and a heavy bodied glue applied to weld all joints
- Where required by the county health department, post installation inspections by the designer must be scheduled 5 weekdays in advance
- Trenches shall be carefully excavated so the bottom has no more than ¼" fall in 10 feet, with no high or low areas within. If high or low areas do exist after trench excavation, high areas should be removed rather than filling in low areas. **Do not over excavate trenches!** Any fine grading should be completed by hand with a rake and shovel, leaving no loose material.
- All pipe openings in the tanks shall be properly grouted. This also applies to the joints around the rise.
- Earth dams, constructed of relatively impervious material, shall be installed at the beginning and end of each lateral to prevent unwanted lateral water movement.
- No heavy equipment shall be used on the field during or after installation. The use of a small loader (i.e. Bobcat) or a trencher (i.e. Ditch Witch 2300/2310) may be used for installation
- Elevations at pin flag locations should be checked by the installer prior to beginning trenches to ensure accuracy
- If septic tank risers are used, they should be a minimum of 6" above finished grade or within 6" of final grade if buried
- Design precludes use of foundation drains on the residence

See Design Specification Sheet for Onsite Wastewater System information

- **If grading for slab foundation is utilized, do not grade/create greater than 2 feet of elevation difference within 15 feet of any component of the septic or repair. If back filling, do not backfill over any initial or repair septic line**

RECEIVED APR 2 5 2022

APPLICATION MUST BE FILLED OUT COMPLETELY & BE LEGIBLE OR IT WILL NOT BE PROCESSED

BB SL

Iredell County Health Department – Environmental Health Division

PAGE 1: *APPLICATION FORM* AP-325618 $500.00

Application For: ( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment
( ) Septic Improvement Permit ( ) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED. APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: ( ) Survey Plat, scaled no more than 1 inch = 60 feet
Place an (X) beside whichever is submitted if applicable ( ) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information: (PRINT CLEARLY)

Applicant Name: Ridgewater Construction LLC Address: PO Box 4211 Mooresville, NC Zip: 28117
Applicant Email: Rachael@ridgewatercustomhomes.com Phone: 704-657-4876 Alt. Phone: _____
Owner Name: Ridgewater Construction LLC Address: P.O Box 4211 Mooresville, NC Zip: 28117
Owner Email: same ↑ Phone: _____ Alt. Phone: _____

Property Information:

Street Address: 116 Witherspoon Ln.
Subdivision Name: laid acres Section/Phase: _____ Lot Number: 62
Driving Directions: 77 N to exit 45, take Rt (L) onto _____

Site Development Information: *(check or complete ALL that apply*

(X) New Single Family Residence
( ) New Multi-Family Residence
( ) Accessory Building
( ) Bedroom(s) Addition
( ) Repair to failing septic system ___ Tank ___ Drain lines Describe Problem: _____
Maximum Number of Bedrooms: 3
Maximum Number of Occupants: _____
( ) Swimming Pool
( ) Other Addition/Structure: _____
Non-Residential Site Development: Type of Business: _____
Square Footage of Building: _____ Max. Number of Employees: _____ Max. Number of Seats/Beds/Other: _____

CHECK FOUNDATION TYPE
( ) Crawl Space Foundation
(X) Concrete Slab Foundation
( ) Basement with Plumbing
( ) Basement without Plumbing

Water Supply: ( ) Replacement Well – Reason: _____
( ) Multi-connection Well Number of Houses: _____ Number of Persons: _____
(X) New Well ( ) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* Year existing system installed: _____
( ) No Preference ( ) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional ( ) Other: _____

Please answer the following to the best of your ability:
( ) Yes (X) No Does the site contain any jurisdictional wetlands?
( ) Yes (X) No Is any non-domestic sewage (i.e. industrial) to be generated?
( ) Yes (X) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: Rachael Mc _____ 4/25/2022
Property owner or owner's legal representative signature (SIGNATURE REQUIRED) DATE

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

(Check and sign only ONE of the options below)

☐ **1. * APPLICANT AND OWNER ARE THE SAME. *** (*Sign here*) _____

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative: *Power of Attorney; Real Estate Contract; Estate executor; Bankruptcy trustee; Court ordered guardianship*
In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:
Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form. If there are multiple property owners, then all property owners must sign the form that designates a legal representative.
By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department.

☐ **2.** I, Rachael McClure, am the legal owner(s) of the property located at 116 Witherspoon Ln. Statesville, NC, identified as PIN (Parcel Identification Number)_____, located in Iredell County, North Carolina.

I do hereby authorize (**print legal representative/company name**) Tarah Wallace, _____, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.

Rachael McClure
Signature of Owner(s)

4/25/2022
Date

Mooresville - Environmental Health

Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115


Statesville - Environmental Health
ronda.hart@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677

IREDELL COUNTY HEALTH DEPARTMENT

ENVIRONMENTAL HEALTH DIVISION

PAGE 2: *SITE PLAN WORKSHEET*

SEE THE "SAMPLE SITE PLAN" BELOW. *INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!*



Place an (X) beside each item as you complete the site plan:

( ) **Property Line measurements are clearly identified**
( ) **All proposed structures are indicated**
( ) **Front and side setbacks from property line**
( ) **Preferred driveway location and well location**
( ) **Area you prefer your septic system to be placed**
( ) **North arrow, or other sufficient indicator of direction**

Circle N/A on the following if appropriate:

Location of septic systems and wells within 100' of your property	**N/A**
Location of easements and rights of ways on your property	**N/A**
Location of any designated wetlands on the property	**N/A**

USE THIS SPACE TO DRAW YOUR SITE PLAN

Show: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site

See attached

Signature: Rachael Neal

Property owner or owner's legal representative signature (SIGNATURE REQUIRED)

4/25/2022

DATE


LTE

Scanned from a M...

PRELIMINARY PLAN
NOT FOR RECORDATION
CONVEYANCES
AND/OR SALES

Septic System Repair
Area Exempt Due To
Property Being Deeded
And Recorded In 1973

Well Site: Stay A minimum of (50ft.)
Away From All Septic & Repair Areas
And (25ft.) Away From All Structures



TAX ID: 4782-03-7028
LOT 2
BONNIE SUE T MOOSE IJV TR &
HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

TAX ID: 4782-03-8028
LOT 1
BONNIE SUE T MOOSE IJV TR &
HUGH L MOOSE FAMILY TR
DB: 2830 PG: 1405
PB: 11 PG: 39

*Neighbors Septic System (Lot #1)

Set ½" Rebar

Old S71°20'43"E 100.00'

LOT 12
0.46 Acres

Proposed Well Site

Proposed House Box

N25°59'29"E 200.14'

S25°59'29"W 200.21'

N71°18'37"W 99.99'

PPBPS Repair . 3 (10ft.)

PPBPS Repair . 3 (10ft.)


Blue Pink Red Yellow

Witherspoon Ln
60' Public R/W
PB: 11 Pg

Red (C

U Ln
R/W
39

2018 IRC COMPLIANT



KEY NOTES:

1. 39" WIDE REFRIGERATOR SPACE, (INSTALL WATER LINE)
2. COUNTERTOP OVER 36" HIGH BASE CABINET.
3. UPPER CABINETS (TOP AT 8'-0" A.F.F.)
4. 30" WIDE RANGE WITH MICRO OR HOOD ABOVE (VENT TO EXTERIOR AND PROVIDE AIR INTAKE)
5. DOUBLE SINK WITH DISPOSAL AND SPRAYER
6. DISHWASHER
7. LAZY SUSAN
8. NOT USED
9. STAIR HANDRAIL PER CODE REQ. (NOT SHOWN FOR CLARITY)
10. (4) 16" SHELVES STARTING @ 24" ABOVE FINISHED FLOOR
11. 20 MINUTE FIRE RATED SELF CLOSING DOOR
12. NOT USED
13. FINISH BELOW STAIRS

SQUARE FOOTAGE SCHEDULE:	
MAIN LEVEL:	984
UPPER LEVEL:	1259
GARAGE:	408
TOTAL FINISHED SQ. FT:	2243

MAIN FLOOR PLAN

SCALE 1/4"

Acknowledgement of Plans Submittal ONLY!

Date 2.15.22

Date 2/24/22

Lloyd Acres 52A/#12

116 Witherspoon Lane

© COPYRIGHT 2018 ARCHWAY DESIGNS LLC. DUPLICATION OF THIS PLAN IS STRICTLY PROHIBITED BY LAW. FOR LEGAL COPIES OF THIS PRINT CONTACT ARCHWAY DESIGNS LLC @ 561-880-2408

ARCHWAY DESIGNS L.L.C. ARE PROFESSIONAL HOME DESIGNERS AND ARE NOT LICENSED ARCHITECTS OR ENGINEERS AND THEREFORE DO NOT HOLD ANY RESPONSIBILITY FOR THE STRUCTURAL INTEGRITY OF THIS PLANS. ALL PLANS SHOULD BE STAMPED BY A LICENSED PROFESSIONAL ENGINEER PRIOR TO CONSTRUCTION

ARCHWAY DESIGNS L.L.C.
ARCHITECTURAL DESIGN AND DRAFTING
www.archwaydesigns.com

PLAN STATUS

PRELIMINARY DRAWINGS DATED:

1ST DRAFT DATED:

FINAL DRAFT DATED:

PERMIT SET DATED: 9/23/19

REVISIONS:

DATE:

DATE:

DATE:

DATE:

DATE:

WHIDBEY BASE PLAN

ADDRESS:

PAGE: A 5

2018 IRC COMPLIANT


© COPYRIGHT 2018 ARCHWAY DESIGNS L.L.C. DUPLICATION OF THIS PLAN IS STRICTLY PROHIBITED BY LAW. FOR LEGAL COPIES OF THIS PRINT CONTACT ARCHWAY DESIGNS L.L.C @ 801-980-2600

ARCHWAY DESIGNS L.L.C. ARE PROFESSIONAL HOME DESIGNERS AND ARE NOT LICENSED ARCHITECTS. ON OCCASION WE MAY SUBMIT THESE DO NOT HOLD ANY RESPONSIBILITY FOR THE STRUCTURAL INTEGRITY OF THIS BUILDING. ALL PLANS SHOULD BE STAMPED BY A LICENSED PROFESSIONAL ENGINEER PRIOR TO CONSTRUCTION

ARCHWAY DESIGNS L.L.C.
ARCHITECTURAL DESIGN AND DRAFTING
www.archwaydesigns.com

KEY NOTES:

1. 90% MIN. EFFICIENT DIRECT VENT DOWNDRAFT GAS FURNACE
2. 40 GALLON GAS WATER HEATER WITH TEMPERATURE SAFETY VALVE ON 18" TALL PLATFORM. INSTALL SEISMIC STRAPS PER CODE REQ.
3. FLUE
4. COUNTERTOP OVER 36" HIGH BASE CABINET.
5. WASHER AND DRYER HOOKUPS (WASHER IS ON THE LEFT)
6. SHELF OR CABINETS ABOVE WASHER AND DRYER
7. 40" TALL HALF WALL WITH WOOD OR MDF CAP (TYP @ STAIRWELL SURROUND
8. COUNTERTOP OVER 32" HIGH BASE CABINET
9. 60" X 30" TUB / SHOWER (2.5GPM SHOWER HEAD)
10. 36" X 60" TUB IN TILE OR SYNTHETIC SURFACE PLATFORM
11. 36" X 60" TILE OR SYNTHETIC SURFACE SHOWER WITH SAFETY GLASS ENCLOSURE
12. (4) 16" SHELVES STARTING @ 24" ABOVE FINISHED FLOOR
13. 12" SHELF AND ROD
14. (2) 12" SHELVES AND (2) RODS
15. MECHANICAL CLOSET IS A STORAGE CLOSET WHEN THE FULL BASEMENT OPTION IS USED.
16. 24" X 30" ATTIC ACCESS.
17. 24" X 48" SKY LIGHT.



UPPER FLOOR PLAN

SCALE 1/4"

Acknowledgement of Plans Submittal ONLY!

Date 2-15-22

Date 2/24/22

PLAN STATUS

PRELIMINARY DRAWINGS DATED:

1ST DRAFT DATED:

FINAL DRAFT DATED:

PERMIT SET DATED: 9/23/18

REVISIONS:

DATE:
DATE:
DATE:
DATE:
DATE:

WHIDBEY BASE PLAN

ADDRESS:

PAGE: A 6