feet deep at the back property line. Remove the nitrification lines of the low pressure pipe system and then install a T & J Panel System in the area of and below the present low pressure pipe system. The depth to the top of the panel should be about 24 inches from the present ground surface.

After the system is installed the surface should be smoothed and seeded to grass to prevent surface water from collecting and standing over the system.

JWC/kd