BLDR 2022-11214

ICHD - ENVIRONMENTAL HEALTH DIVISION

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625

PERMIT # OSWP-2022-6600

SEPTIC: IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4774-08-8929

APPLICANT / OWNER: HELMSMAN HOMES LLC | APPLICANT ADDRESS: PO Box 3965, MOORESVILLE, NC 28117

SITE ADDRESS: 145 SALEM SPRINGS LN, STATESVILLE, NC 28625 | PHONE: (980) 500-1251 | ALT. PHONE: (980) 500-1251

SITE DIRECTIONS: Hwy 64 to New Salem to Salem Springs. | SAP CONTROLLED: YES ☐ NO ☑

SUBDIVISION: Salem Springs | SECTION: — | LOT #: 4/4 | LOT AREA: 1.612 Ac | DESIGN FLOW: 360 | L.T.A.R.: .30

Septic Tank: (gal) 1000	STB:	Date:	☑ New System ☐ Repair ☐ Expansion	System Type: III	☑ Residence	No. Bedrooms: 3	Water Supply: Other Public Water
Pump Tank: (gal)	PT:	Date:	System Description: Gravity - 25% Reduction		☐ Business	No. Persons: 6	
Pump Make:	Model:	Serial #:	Repair System Description: LP-PPBPS - 50% Reduction		☐ Other	No. Employees:	
# Nitrification Fields: 1	# Lines: 3	Linear Ft.: 300	Maintenance Agreement Required: ☐ YES ☐ NO		☑ Slab	☐ Crawl Space	
Trench Width: 36 in	Trench Bottom Depth (Low side): 30 in		Gravel Depth: —	☐ GRAVITY ☐ PRESSURE	☐ Basement w/ Plumbing	☐ Basement w/o Plumbing	

Comments / Conditions:

INITIAL SITE SKETCH

This permit is issued to pursuant to G.S. 130A-335 (a2), (a3), (a4) using the Signed + Sealed LSS/LG Evaluation attached here from:

Soil + Forestry Services of the Carolinas, PA

LS#1231

AS BUILT SKETCH

LINES MW 10/08/24

TANKS

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT with plat valid without expiration. ☑ IMPROVEMENT PERMIT with site plan valid for 60 mos. ☑ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.

Owner / Applicant Signature: _____ Date: _____

IMPROVEMENT PERMIT by: Benjamin A Bolton Date: 12-9-2022

AUTHORIZATION TO CONSTRUCT by: Benjamin A Bolton Date: 12-9-2022

Installed By: VADA ENTERPRISE

OPERATION PERMIT by: [signature] Date: 10/14/24

Existing System Inspected By: _____ Date: _____

FOR SEPTIC FINAL INSPECTION CALL: 704-664-3703 BETWEEN 8am-9am the day the inspection is needed.

County: Iredell

This Section for Local Health Department Use Only

Initial submittal received: 12/9/2022 (Date) by BB (Initials)

Permit Number: OSWP-2022-6600

G.S. 130A-335(a6) states the following: *'If a local health department fails to act on an application for a construction authorization submitted pursuant to subsection (a5) of the section within 10 business days of receipt of a complete application, the local health department shall issue the construction authorization.'*

In accordance with G.S. 130A-335(a5) the construction authorization application is:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing: _____

_____

Copies of this were sent to the AOWE/PE and the Owner on _____ (Date)

State Authorized Agent: _____ Date: _____

☐ Denied (See attached report.)

Copies of this were sent to the AOWE/PE and the Owner on _____ (Date)

State Authorized Agent: _____ Date: _____

☑ Complete

State Authorized Agent: Benjamin A Bolt Date of Issuance: 12-9-2022

This Construction Authorization is issued pursuant to G.S. 130A-335(a2), (a5), and (a6) using the signed and sealed plans or evaluations attached here. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes, or if information submitted in the application was falsified, inaccurate or misleading. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. The location and identification of all property lines, easements, water lines, and other appropriate utilities shall be the responsibility of the owner. Final landscaping shall be constructed to divert water and establish vegetative cover.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to plans, evaluations, preconstruction conference findings, submittals, or actions from a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator in GS 130A-335(a2), (a5), and (a7). The Department, the Department's authorized agents, and the local health departments shall be responsible and bear liability for their actions and evaluations and other obligations under State law or rule, including the issuance of the operations permit pursuant to GS 130A-337.

Construction Authorization Expiration Date: 12-9-2027

See attached site sketch

County: Iredell

This Section for Local Health Department Use Only

Initial submittal received: 12/9/2022 (Date) by BB (Initials)

Permit Number: OSWP-2022-6600

G.S. 130A-335(a4) states the following: *'If a local health department fails to act on an application for an improvement permit submitted pursuant to subsection (a3) of the section within 10 business days of receipt of a complete application, the local health department shall issue the improvement permit.'*

In accordance with G.S. 130A-335(a3) the improvement permit application is:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

_____

_____

Copies of this were sent to the LSS and the Owner on _____ (Date)

State Authorized Agent: _____ Date: _____

☐ Denied (See attached report.)

Copies of this were sent to the LSS and the Owner on _____ (Date)

State Authorized Agent: _____ Date: _____

☑ Complete

State Authorized Agent: Benjamin A. Bobbitt Date of Issuance: 12-9-2022

This Improvement Permit is issued pursuant to G.S. 130A-335 (a2), (a3), and (a4) using the signed and sealed LSS/LG evaluation(s) attached here. The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes, or if information submitted in the application was falsified, inaccurate or misleading. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. The location and identification of all property lines, easements, water lines, and other appropriate utilities shall be the responsibility of the owner.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to evaluations, submittals, or actions from a licensed soil scientist or licensed geologist pursuant to GS 130A-335(a2).

Improvement Permit Expiration Date: 12-9-2027

See attached site sketch

County: Iredell

CONSTRUCTION AUTHORIZATION FOR G.S. 130A-335(a2)/SL2022-11

PIN/Lot Identifier: 4774088929 - Lot 44

Issued To: Salem Springs Development, LLC

Property Location: Salem Springs Lane, Statesville NC 28625

AOWE/PE Plans/Evaluations Provided: Yes ☑ No ☐ If yes, name and license number of AOWE/PE: Samuel Ashley Rollans 10027

Facility Type: Single Family Home

☑ New ☐ Expansion ☐ Repair System Relocation ☐

Basement? ☐ Yes ☑ No Basement Fixtures? ☐ Yes ☐ No

Type of Wastewater System** Accepted 25% Reduction (Initial) PBPS - Low Pressure (Repair)

Design Daily Flow: 360 GPD Wastewater Strength: ☑ domestic ☐ high strength ☐ industrial process

Session Law 2014-120 Section 53, Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies? ☐ Yes ☑ No

Installation Requirements/Conditions

Septic Tank Size: 1,000 gallons Total Trench/Bed Length: 300 feet Trench/Bed Spacing: 9 feet on center

Drainfield square footage: 1,080 Trench/Bed Width: 36 inches LTAR: 0.3 gpd/ft²

Soil Cover: 6 min inches Slope Adjusted Maximum Trench/Bed Depth: 30 inches Low Side

Aggregate Depth: ____ inches above pipe ____ inches below pipe ____ inches total

Pump Tank Size (if applicable): ____ gallons Requires more than 1 pump? ☐ Yes ☐ No

Pump Requirements: ____ ft. TDH vs. ____ GPM Grease Trap Size (if applicable): ____ gallons

Distribution Method: ☑ Serial ☐ D-Box or Parallel ☐ Pressure Manifold(s) ☐ LPP ☐ Other: ____

Artificial Drainage Required: Yes ☐ No ☑ If yes, please specify details: ____

Legal Agreements *(If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)*

Multi-party Agreement Required [.1937(h)]: Yes ☐ No ☑

Easement, Right-of-Way, or Encroachment Agreement Required [.1938(j)]: ☐ Yes ☑ No

Declaration of Restrictive Covenants: ☐ Yes ☑ No

****If applicable:**

I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Print Name: ____

Owner/Legal Representative Signature: ____ Date: ____

Pre-Construction Conference Required: Yes ☐ No ☑

Conditions: ____

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

AOWE/PE Print Name: Samuel Ashley Rollans

AOWE/PE Signature: Samuel A Rollans Date: 9/27/22

This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).

See attached site sketch

County: Iredell

IMPROVEMENT PERMIT FOR G.S. 130A-335(a2)/SL2022-11

PIN/Lot Identifier: 4774088929 - Lot 44

Issued To: Salem Springs Development, LLC,

Property Location: Salem Springs Lane, Statesville NC 28625

Subdivision: Salem Springs Lot #: 44 Block: _____ Section: _____

LSS Report Provided: Yes ☑ No ☐

If yes, name and license number of LSS: Samuel Ashley Rollans #1231

New ☑ Repair ☐ Expansion ☐ System Relocation ☐

Proposed Structure: Single Family Home

Proposed Wastewater System Type: Accepted 25% Reduction (Initial) PPBPS - Low Pressure (Repair)

Fill System: ☐ Yes ☑ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area please provide a fill plan)

Proposed Design Daily Flow: 360 GPD Proposed LTAR (Initial): 0.3 Proposed LTAR (Repair): 0.225

Design Wastewater Strength: ☑ domestic ☐ high strength ☐ industrial process

Number of bedrooms: 3 Number of Occupants: 6 Other: _____

Pump Required: ☐ Yes ☑ No ☐ May be required based upon final location and elevations of facilities

Artificial Drainage Required: ☐ Yes ☑ No If yes, please specify details: _____

Type of Water Supply: ☐ Private well ☐ Public well ☑ Municipal Supply ☐ Spring ☐ Other: _____

Drainfield location meets requirements of Rule .1945: Yes ☑ No ☐

Drainfield location meets requirements of Rule .1950: Yes ☑ No ☐

Permit valid for: ☑ Five years [site plan submitted pursuant to GS 130A-334(13a)] ☐ No expiration [plat submitted pursuant to GS 130A-334(7a)]

Permit conditions:

Licensed Soil Scientist Print Name: Samuel Ashley Rollans

Licensed Soil Scientist Signature: Samuel A Rollans Date: 9/27/22

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

See attached site sketch

SOIL & FORESTRY SERVICES
OF THE CAROLINAS, PA

www.soilandforestryservices.com

Project#: 21-0029
September 26th, 2022

SALEM SPRINGS DEVELOPMENT, LLC
Attn: *Paul Penninger*
Email: ppenninger@nesthomes.com

RE: Soil& Site Evaluation for a 3 Bedroom Residence on Lot 44 Salem Springs Subdivision, 1.612ac Parcel, PIN# 4774088929, Salem Springs Lane, Statesville, NC 28625.

Mr. Penninger:

At your request Soil & Forestry Services of the Carolinas (S&FS) has performed soil/site evaluations on parcel noted above. The Lot size is noted on the attached survey map & soil evaluation form. The purpose of our work was to identify soil areas with potential to support subsurface wastewater disposal systems and provide design details for Session Law submittal to Iredell County Health Department.

Site Conditions

At the time of our evaluation land cover on the property was mostly open field. Topography within the evaluated area was gentle slope near the house site and proposed drainfield area. A terrace in the system area should be graded to allow for positive drainage. Property lines and corners were marked at the time of the evaluation by Jordan Grant & Associates Land Surveying. The client provided an Autocad File of a survey as a basemap. The proposed septic layout was located via Trimble Submeter GPS/tape measures and used to produce the attached *Site Plan*. The house envelope was located via Autocad.

Methodology

We evaluated soil areas through the use of backhoe pits. Soil morphological conditions including color, texture, structure, etc. were reviewed in the field with nine pit locations on the property flagged and located via GPS. Four of the eight backhoe pits are located in or adjacent to the proposed septic layout. Soil suitability was determined by referencing 15A NCAC 18A.1900 "Laws and Rules for Sewage Treatment and Disposal Systems". *Soil & Site Evaluation Forms* were utilized to record the soil morphological data for each pit. The house envelope was located via Autocad. An on-ground layout of system and repair was performed using a laser level. Pin flag locations of the layout were also located by GPS and tape measures. Detailed system & repair information is summarized in the following paragraph for this Lot.

Salem Springs Lot 44 (*See Attached Design*)
The septic layout for this lot (9' centers) yielded a total of 644 linear feet of line. The primary system is proposed as 300 linear feet of Accepted (25% Reduction) drainfield with gravity distribution. Trench depth (Low Side) is specified at 30 inches. The repair system is proposed as 219 linear feet of Mod. Conv. (PPBPS) drainfield with low pressure distribution. There is 344 linear feet available for repair. Trench depth (Low Side) is specified at 34 inches.

Session Law Requirements

All information needed to issue the IP must be submitted with the application. The application shall include all information described in 15A NCAC 18A .1937(d) and be accompanied by a signed and dated statement from the applicant (owner or owner's legal representative) that reads as follows:

"The LSS/LG evaluation(s) attached to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3)."

Owner Date

Print Name Tim Carr


Signature Tim Carr 10/11/2022

The LSS evaluation shall include a statement bearing the LSS seal and signature that reads as follows:

"The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2)."

Disclaimer
This report reflects the findings of S&FS, PA. *This LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2)."* Any site modifications that impact the proposed septic areas on the site may nullify this design for Lot 44 Salem Springs Subdivision. System design requirements and site requirements shall be adhered to for installation and Operations Permits to be issued by the local Health Department. If you have questions regarding these requirements a Pre-Construction meeting should be scheduled to discuss. Please contact S&FS if you have any questions regarding this report or the attached information. S&FS also offers septic system inspection, wetland delineation and forestry services.

Sincerely,



S. Ashley Rollans, LSS
Attachment: *Septic Design*

SOIL & FORESTRY SERVICES
OF THE CAROLINAS, PA

www.soilandforestryservices.com

Attached is a proposed design for an Accepted Septic System with gravity dist. for a 3 bedroom single family residence on Lot 44 Salem Springs Subdivision, Statesville 28625, Iredell County, NC. PIN#: 4774088929

Contents: **Page**

Information for the Installer---------- 1

Design Information
- Design Specifications---------- 2-3
- Layout Specifications---------- 4

Site Plan/System Plan---------- 5

Calculations---------- 6

Profile Descriptions---------- 7-8

Application---------- ONLINE

Green Sheet---------- ONLINE

Agent Authorization Form---------- ONLINE

LICENSED SOIL SCIENTIST Samuel A. Rollins 1231 STATE OF NORTH CAROLINA

September 26, 2022
Project #: 21-0029
Design By: Soil & Forestry Services of the Carolinas, PA

INFORMATION FOR THE INSTALLER:

The permit should be read very carefully prior to bidding. The following are details that must be considered along with all other considerations.

- Tanks shall be approved by NC DHHS, and certification supplied by the manufacturer.
- Tanks shall be water tested prior to installation.
- The installer shall be responsible to the owner for placement of the tanks and to insure that final grades are returned to the original natural grade, with exception of added structural features.
- The supply trench shall be compacted to eliminate cavities left during initial fill placement.
- Installation of the system shall be during dry conditions in order to protect the soil structure.
- All fittings shall be pressure rated fittings.
- All joints shall be cleaned with PVC pipe cleaner and a heavy bodied glue applied to weld all joints.
- Where required by the county health department, post installation inspections by the designer must be scheduled 5 week days in advance.
- Trenches shall be carefully excavated so the bottom is within 2" from the highest to . the lowest points of elevation within the trench. If the bottom elevation needs adjusting after it has been trenched, it will be done by removing high points rather than filling low points. It is extremely important to insure that trenches are not over excavated during initial trenching. All fine grading within the trench will be hand done with a shovel. No loose material will be left in the trench
- All pipe openings in the tanks shall be properly grouted. This also applies to the joints around the riser.
- All tanks shall be properly back filled and compacted to prevent slump at a later date.
- Earth dams, constructed of relatively impervious material, shall be installed at the beginning and end of each lateral.
- No heavy equipment shall be used on the field during or after installation. The use of a small loader (i.e. Bobcat) or a trencher (i.e. Ditch Witch 2300/2310) may be used for installation.
- Elevations at pinflag locations should be checked by the installer prior to beginning trenches.
- Septic tank riser shall be a minimum of 6" above finished grade.
- System is specified as a gravity 25% reduction (Accepted) installation.
- Repair is specified as a PPBPS installation w/low pressure distribution.

GRAVITY ACCEPTED SYSTEM
FOR WASTEWATER TREATMENT

Owner/Applicant:	Salem Springs Development, LLC
Address:	P.O. Box 3965 Mooresville, NC 28117
Phone:	704.202.1524
County:	Iredell
Location:	Salem Springs Lot 44
Source of Wastewater Flow:	3 Bedroom Single Family Residence
Estimated Gallons Per Day Flow:	360
System Flow:	N/A

Design Specifications

Drainfield Size:	300	
Loading Rate (gpd/ft.^{2}):	0.3	
Depth of Gravel in Trench:	N/A	
Gravel Size:	N/A	
Max.Trench Depth (LOW SIDE):	30 in.	Repair Trench Bottom 34 in.
Trench Width:	36 in.	
Septic Tank Size:	1000	
Estimated Supply Line Length:	55	
Supply Line Diameter:	4 in. SCH 40 PVC	
Supply Line Volume:	35.92	
Dosing Volume:	N/A	
Supply Manifold:	N/A	
Supply Manifold Length:	N/A	
Supply Manifold Volume:	N/A	
Recommended Float Controls:	N/A	
Recommended Control Panel:	N/A	
Pressure Head:	N/A	
Friction Head:	N/A	
Elevation Head:	N/A	
Total Dynamic Head:	N/A	
Threaded Union:	N/A	
Gate Valves:	N/A	
Check Valves:	N/A	
Anti-Siphon Hole:	N/A	
Additional Comments:	Soil suitability was performed by Soil & Forestry Services of the Carolinas, PA	

Salem Springs

ACCEPTED SYSTEM

DESIGN FLOW (gpd):	360
SOIL APPLICATION RATE (gpd/ft.^{2}):	0.3
TOTAL AREA TRENCH BOTTOM:	900
TOTAL LATERAL LENGTH:	300
NUMBER OF FIELDS:	1
LATERAL LENGTH REQUIRED PER FIELD:	300
SUPPLY LINE LENGTH:	55
TOTAL DYNAMIC HEAD:	N/A
MANIFOLD SIZE:	N/A
DOSING VOLUME:	N/A
PUMP TANK DRAW DOWN*:	N/A
SEPTIC TANK SIZE:	1000

Layout Specifications - - Salem Springs Lot 44

Project #: 21-0029

LAYOUT FOR 3 BEDROOM HOME

September 26, 2022

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM							
INSTR. 1							
1	RED					51	51
2	ORANGE					62	62
3	YELLOW					62	62
4	BLUE					60	60
5	RED					60	60
6	***ORANGE***					***99***	***96***
7	***YELLOW***					***97***	***96***
8	***BLUE***					***110***	***108***
9	RED					43	43
					Total	644	638


	LINE LENGTH	LTAR GPD/FT2	SYSTEM TYPE	SOIL LTAR GPD/FT2	TRENCH SYSTEM	DISTRIBUTION	LOW SIDE TRENCH DEPTH
**** System***	***300***	***0.300***	***ACCEPT.***	***0.300***	***25% RED***	***GRAVITY***	30"
Repair	344	0.275	MOD CONV	0.275	PPBPS	LOW PRESSURE	34"

Notes: **All measures in feet

**Nitrification lines are demonstrated on contour via colored pin flags

**Nitrification lines were located by GPS and tape measure.

**Property corners & lines located by survey (Jordan Grant & Associates)


SPRINGS LANE
DRIVE
HOUSE
LOT 44
1.612 AC.
35' RY
15' SY
459.30'
N 64° 16' 06" W
S 82° 55' 52" W
487.87'
SCALE
1" = 50'
NORTH
L43
C2
C33
C4
C29
L27
L166
L165
L171
L168
L180
L28
L163
L164
C7
C28
C36
26
L157
P1
P2
P3
P5
P6
P7
P8
P9
P65
P66
P73
51.2'
39.6'
50'
15.3'
1 R 51'
0 62'
Y 62'
B 60'
R 60'
0 99' Install 96'
Y 97' Install 96'
8 B 110' Install 108'
9 R 43'

CALCULATIONS

Location	Salem Springs	
Project Number	21-0029	
Lot No:	44	
No. of Bedrooms	3	
Design Flow	360	$^{gal}/_{day}$
LTAR	0.300	$^{gal}/_{ft^2\,day}$
PPBPS? (YES OR NO)	NO	
Supply Line Length	55	ft.
Supply Line Volume	35.915	gal.
Required Feet of Line	300	ft.
Amount of Line from Layout	300	ft.
Gallons per Minute	N/A	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Septic Tank Size	1000	gal.
Panel Volume	N/A	gal.
# of Panels	N/A	
Dosing Volume	N/A	gal.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42

Tank Draw Down	N/A	
Pump Run Time		
Elevation Head	N/A	ft.
Pressure Head	N/A	ft.
Friction Factor	N/A	ft./100 ft. *(From the interpolater.)*
Friction Head	N/A	ft.
Total Dynamic Head (+15%)	N/A	ft.

PROPERTY ID #: 4774088929
COUNTY: Iredell

SOIL/SITE EVALUATION
***for* ON-SITE WASTEWATER SYSTEM**
(Complete all fields in full)

OWNER: Salem Springs Development, LLC APPLICATION DATE
ADDRESS: P.O. Box 3965 Mooresville, NC 28117 DATE EVALUATED: 8/11/22
PROPOSED FACILITY: 3BR PROPOSED DESIGN FLOW (.1949): 360gpd PROPERTY SIZE: 1.61ac
LOCATION OF SITE: Salem Springs subd Lot 44 PROPERTY RECORDED: yes
WATER SUPPLY: ☐ Private ■ Public ☐ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring ■ Pit ☐ Cut TYPE OF WASTEWATER: ■ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
1	L/5%	0-10	BSCLWFSBK	FRSSSP	COM FE DEPL CHROM2 21 FEW SAP	60			PS 0.1 DRIP
		10-42	BRCWFSBK/ABK	FRSSP					
		42-60	BRCWMSBK	FRSSP					
2	L/5%	0-13	BSCLWFSBK	FRSSSP	FE DEPL FE DEPL CHROMO2 28-52 FEW AP	64			PS 0..1 DRIP
		13-26	YBCWMSBK/ABK	FRSSP					
		26-52	YRCWFSBK	FRSSSP					
		52-64	BRCWMSBK/ABK	FRSSP					
3	L/5%	0-9	BSCLWFSBK	FRSSSP	COM FE DEPL CHROMO2 19 FEW SAP/LITHO	69			PS 0.1 DRIP
		9-53	RBCWFABK	FRSSSP					
		53-69	RBCWFABK/SBK	FRSSS					
4	OLD PIT REFER NOTES Area not used								

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)	Accepted	PPBPS
Site LTAR	0.3	0.275

OTHER FACTORS (.1946):
SITE CLASSIFICATION (.1948): ps
EVALUATED BY: Ashley Rollans
OTHER(S) PRESENT: Mason Freeman

COMMENTS:

SOIL/SITE EVALUATION

(Continuation Sheet-Complete all field in full)

PROPERTY ID #: same

DATE OF EVALUATION: same

COUNTY: same

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
P 5	L/5%	0-17	BSCLWFSBK	FRSSSP	FEW FE DEPL 27+ COM FE & CHROMO2 30+	67			PS 0.225 AT GRAD, 0.1 DRIP
		17-30	RBCWMSBK/ABK	FRSSP					
		30-67	BRCWMABK/SBK	FRSSSP					
P 6	L/5%	0-11	BCLWFSBK	FRSSSP		63			PS 0.275
		11-63	BRCWMSBK/ABK	FRSSSP					
P 7	L/5%	0-10	BCLWFSBK	FRSSP	FEW FE DEPL	57			PS 0.25
		10-39	BRCWFABK/SBK	FRSSP					
		39-57	RBCWMSBK	FRSSP					
P 8	L/5%	0-6	BCLWFSBK	FRSSP	FEW SAP	62			PS 0.3
		6-35	BRCWFABK/SBK	FRSSP					
		35-62	RBCWMSBK/ABK	FRSSP					
P 9	L/5%	0-6	BCLWFSBK	FRSSP		59			PS 0.3
		6-46	RBCWMSBK/ABK	FRSSP					
		46-59	RBC/CLWMSBK	FRSSP					

COMMENTS: